STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 53

SHSM = FHWA 2004 STANDARD HIIGHWAY SIGNS AND MARKINGS BOOK AND THE 2012 SUPPLEMENT TO THE 2004 EDITION

MILE MARKER, DIRECTION	SIGN LEGEND	SIGN DIMENSIONS EA.	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (in) 3.0 lb/ft 1.3	4.0 1.7	4.0Mod 1.7	TUBULAR STEEL DIA (in) FND-ATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL SHSM	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
INT #5 0.206 RAMP B RT	1 GAS 24HR 1 DIESEL	1 1	72 72	10 10	5.00 5.00																															148 148	
	1 FOOD 3 LODGING	1 1	72 72	10 10	5.00 5.00																															148 148	
	WRONG WAY	1	36	24	6.00						2												2	166.5									BACK TO BACK	R5-1a		
0.206 RAMP B LT	WRONG WAY	1	36	24	6.00						2					X		2																R5-1a		
0.233 RAMP B RT	STOP / DO NOT ENTER	1 1	30 30	30 30	6.25 6.25																												BACK TO BACK	R1-1 R5-1		
	ONE WAY / ONE WAY	1 1	36 36	12 12	3.00 3.00						1					X		1															BACK TO BACK	R6-1L R6-1R		
0.233 RAMP B LT	STOP / DO NOT ENTER	1 1	30 30	30 30	6.25 6.25																												BACK TO BACK	R1-1 R5-1		
	ONE WAY / ONE WAY	1 1	36 36	12 12	3.00 3.00						1					X		1															BACK TO BACK	R6-1L R6-1R		
0.090 RAMP C RT		1	36	36	9.00						2					X		2																W3-1		
0.118 RAMP C RT	TO / TO	1 1	24 24	12 12	2.00 2.00		I																										BLACK ON WHITE GREEN ON WHITE	M4-5 M4-5		
	5 / VERMONT 123	1 1	24 30	24 24	4.00 5.00																													M1-4		E-136B
		1 1	21 21	15 15	2.19 2.19						2												2	180.2								#2B	BLACK ON WHITE GREEN ON WHITE	M6-1 M6-1		
0.147 RAMP C RT	Westminster 3 Bellows Falls 4		72 72	12 12			1 1																													
	Walpole N.H. 4		72	12			1				2												2	176.4												
RAMP C	BRIDGE PLAQUE						I																													
												FT	FT	FT	FT	FT 95.6	FT	EA.		LB	LB	LB		LB 523.1	LB	LB	LB								
		SUBTOTALS SHEET 53	SF 95.38	SF	EA. 3	SF						FT			FT 95.6					LB			EA. 6	LB 523.1				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: **GUILFORD-ROCKINGHAM**
PROJECT NUMBER: **IMG SIGN(44)**

FILE NAME: **z12A528tssint.xlsb**
PROJECT LEADER: **C. GREGORY**
DESIGNED BY: **J. SMITH**
DRAWN BY: **J. SMITH**
CHECKED BY: **D. MUNRO**
PLOT DATE: **4/16/2014**
TRAFFIC SIGN SUMMARY SHEET 53
SHEET **110** OF **157**