STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 56

SHSM = FHWA 2004 STANDARD HIIGHWAY SIGNS AND MARKINGS BOOK AND THE 2012 SUPPLEMENT TO THE 2004 EDITION

MILE MARKER, DIRECTION	SIGN LEGEND	SIGN DIMENSIONS EA.	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (in) 3.0 lb/ft 1.3	4.0 1.7	4.0Mod 1.7	TUBULAR STEEL DIA (in) FND-ATION	3.0 lb/ft 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL SHSM	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
INT #5 0.129 WSH RT	NORTH	1	24	12	2.00																												(INTERSTATE) WHITE ON BLUE	M3-1		
	91	1	24	24	4.00																													M1-1		
	←	1	21	15	2.19						1						X	1															(INTERSTATE) WHITE ON BLUE	M6-1		
0.214 WSH RT	Westminster Hgts Rd	1	69	12	5.75						2					X		2																	146	
0.215 WSH RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					X		1																		E-141
0.542 WSH RT	JCT	1	21	15	2.19																												BLACK ON WHITE	M2-1		
	5	1	24	24	4.00						1					X		1																M1-4		
0.560 WSH RT	25 M.P.H.		36 18	36 18			1 1				2					X		1																W1-1R W13-1		
0.617 WSH RT	Bellows Falls 3 Westminster 2	1 1	72 72	12 12	6.00 6.00																														148 148	
	Walpole NH 3	1	72	12	6.00						2												2	146.0											148	
0.655 WSH RT	NORTH SOUTH	1 1	24 24	12 12	2.00 2.00																												BLACK ON WHITE BLACK ON WHITE	M3-1 M3-3		
	5 5	1 1	24 24	24 24	4.00 4.00																													M1-1 M1-1		
		1 1	21 21	15 15	2.19 2.19																											#2A	BLACK ON WHITE BLACK ON WHITE	M5-1 M5-1		
	TO TO	1 1	24 24	12 12	2.00 2.00																												BLACK ON WHITE GREEN ON WHITE	M4-5 M4-5		
	121 VERMONT 123	1 1	~~24~~ 30 30	24 24	~~4.00~~ 5.00 5.00																													M1-5		E-136B
		1 1	21 21	15 15	2.19 2.19						2												2		289.8							#2C	BLACK ON WHITE GREEN ON WHITE	M5-1 M5-1		
												FT	FT	FT	FT	FT 83.9	FT 15.9	EA.		LB	LB	LB		LB 146.0	LB 289.8	LB	LB									
		SUBTOTALS SHEET 56	SF 76.89	SF	EA. 2	SF						FT			FT 99.8					LB			EA. 4	LB 435.8				EA.	EA.	LB						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: GUILFORD-ROCKINGHAM
PROJECT NUMBER: IMG SIGN(44)

FILE NAME: z12A528tssint.xlsb
PROJECT LEADER: C. GREGORY
DESIGNED BY: J. SMITH
TRAFFIC SIGN SUMMARY SHEET 56

PLOT DATE: 4/16/2014
DRAWN BY: J. SMITH
CHECKED BY: D. MUNRO
SHEET 113 OF 157