STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 66

SHSM = FHWA 2004 STANDARD HIIGHWAY SIGNS AND MARKINGS BOOK AND THE 2012 SUPPLEMENT TO THE 2004 EDITION

MILE MARKER, DIRECTION	SIGN LEGEND	SIGN DIMENSIONS EA.	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (in) 3.0 lb/ft 1.3	4.0 1.7	4.0Mod 1.7	TUBULAR STEEL DIA (in) FND-ATION	3.0 lb/ft 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL SHSM	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
INT #6 0.352 VT 103 RT	SOUTH / NORTH	1	24	12	2.00																												(INTERSTATE) WHITE ON BLUE	M3-3		
		1	24	12	2.00																												GREEN ON WHITE	M3-1		
	INTERSTATE 91 / VERMONT 103	1	24	24	4.00																													M1-1		
		1	30	24	5.00																															E-136B
		1	21	15	2.19		I				2												2	180.2							#2B	(INTERSTATE) WHITE ON BLUE SALVAGE "DETOUR ROUTE 30"	M6-1		
		1	21	15	2.19																												GREEN ON WHITE	M6-3		
0.560 VT 103 RT	NORTH	1	24	12	2.00																												GREEN ON WHITE	M3-1		
	VERMONT 103	1	30	24	5.00		I				1					X			1														SALVAGE "DETOUR ROUTE 30"			E-136B
0.519 VT 103 LT	Springfield 11 White River Jct 37	1	72	12	6.00																														148	
		1	72	12	6.00																														148	
	Brattleboro 28	1	72	12	6.00						2												2	146.0										148	
0.478 VT 103 LT	NORTH / SOUTH	1	24	12	2.00																												(INTERSTATE) WHITE ON BLUE	M3-1		
		1	24	12	2.00																												(INTERSTATE) WHITE ON BLUE	M3-3		
	INTERSTATE 91 / INTERSTATE 91	1	24	24	4.00																													M1-1		
		1	24	24	4.00																													M1-1		
		1	21	15	2.19						2												2	180.2							#2A	(INTERSTATE) WHITE ON BLUE	M6-3		
		1	21	15	2.19																												(INTERSTATE) WHITE ON BLUE	M6-2		
0.429 VT 103 LT		1	18	18	2.25						1				X				1															OM1-1		
0.430 VT 103 LT	SOUTH	1	24	12	2.00																												(INTERSTATE) WHITE ON BLUE	M3-3		
	INTERSTATE 91	1	24	24	4.00																													M1-1		
		1	21	15	2.19						1						X		1														(INTERSTATE) WHITE ON BLUE	M6-2		
											FT	FT	FT		FT 9.5	FT 14.6	FT 15.9		EA.	LB	LB	LB		LB 506.4	LB	LB	LB									
	SUBTOTALS SHEET 66	SF 69.20	SF	EA.	SF		FT								FT 40.0					LB			EA. 6	LB 506.4				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: **GUILFORD-ROCKINGHAM**
PROJECT NUMBER: **IMG SIGN(44)**

FILE NAME: z12A528tssint.xlsb
PROJECT LEADER: C. GREGORY
DESIGNED BY: J. SMITH
TRAFFIC SIGN SUMMARY SHEET 66

PLOT DATE: 4/16/2014
DRAWN BY: J. SMITH
CHECKED BY: D. MUNRO
SHEET 123 OF 157