STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 71

SHSM = FHWA 2004 STANDARD HIIGHWAY SIGNS AND MARKINGS BOOK AND THE 2012 SUPPLEMENT TO THE 2004 EDITION

MILE MARKER, DIRECTION	SIGN LEGEND	SIGN DIMENSIONS EA.	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (in) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0Mod lb/ft 1.7	TUBULAR STEEL DIA (in) FND-ATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL SHSM	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
WELCOME CENTER 10.056 RAMP C RT	BUS PARKING ONLY	1	24	18	3.00						1					X		1																		147	
10.093 RAMP C LT	EXIT	1	24	24	4.00						1					X		1																		147	
10.111 RAMP C RT	BUS PARKING ONLY	1	24	18	3.00						1					X		1																		147	
10.126 RAMP C RT	R	1	30	30	6.25						1					X		1																		R8-3	
10.128 RAMP C LT	EXIT	1	24	24	4.00						1					X		1																		147	
10.131 RAMP C RT	R	1	30	30	6.25						1					X		1																		R8-3	
10.145 RAMP C LT	EXIT	1	30	30	6.25																														146	
	DO NOT ENTER	1	30	30	6.25						1					X		1																	BACK TO BACK	R5-1		
10.146 RAMP C LT	EXIT	1	30	30	6.25																														146	
	DO NOT ENTER	1	30	30	6.25						1						X	1																	BACK TO BACK	R5-1		
	NO PARKING BEYOND THIS POINT	1	24	30	5.00																														R8-1		
10.156 RAMP C LT	ONE WAY	1	36	12	3.00						2					X		2																		R6-1R		
WEIGH ST. NB 20.4 0.054 RAMP A RT	WRONG WAY	1	36	24	6.00						2					X		2																	THINNING & TRIMMING	R5-1a		
0.054 RAMP A LT	WRONG WAY	1	36	24	6.00						2					X		2																		R5-1a		
0.073 RAMP A RT	DO NOT ENTER	1	30	30	6.25						1					X		1																		R5-1		
												FT	FT	FT	FT	FT 193.4	FT 17.6	EA.		LB	LB	LB		LB	LB	LB	LB									
		SUBTOTALS SHEET 71	SF 77.75	SF	EA.	SF						FT			FT 211.0					LB			EA.	LB				EA.	EA.	LB						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: **GUILFORD-ROCKINGHAM**
PROJECT NUMBER: **IMG SIGN(44)**

FILE NAME: z12A528tssrestarea.xlsb PLOT DATE: 4/16/2014
PROJECT LEADER: C. GREGORY DRAWN BY: J. SMITH
DESIGNED BY: J. SMITH CHECKED BY: D. MUNRO
TRAFFIC SIGN SUMMARY SHEET 71 SHEET 128 OF 157