STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 72

SHSM = FHWA 2004 STANDARD HIGHWAY SIGNS AND MARKINGS BOOK AND THE 2012 SUPPLEMENT TO THE 2004 EDITION

MILE MARKER, DIRECTION	SIGN LEGEND	SIGN DIMENSIONS			NEW & SALVAGED SIGNS				EXIST POST		NEW SIGN POSTS																						REMARKS	SIGN DETAIL		
		EA.	WIDTH (in)	HEIGHT (in)	"A"	"B"	SALV SIGN	SALV TIS	RETAIN	SALVAGE	NO. OF POSTS	FLANGED CHANNEL lb/ft			SQUARE STEEL (in) lb/ft			ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (in) lb/ft			FND-ATION	TUBULAR STEEL DIA (in) lb/ft				W-SHAPE STEEL FTG. SIZE		WEIGHT	POST SIZE	SIGN FRAME		SHSM	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												1.12	2.0	3.0	1.75	2.0	2.5			3.0	4.0	4.0Mod		3.0	3.5	4.0	5.0	24"	30"							
															1.88	2.42	3.35			1.3	1.7	1.7		7.6	9.0	10.8	14.6									
WEIGH ST. NB 20.4 0.073 RAMP ALT	PROHIBITED	1	30	24	5.00																														E-144
	DO NOT ENTER	1	30	30	6.25						1					X		1															BACK TO BACK	R5-1		
0.110 RAMP ART	$500 FINE THROWING TRASH ON HIGHWAYS AND STREAMS	1	24	30	5.00						1					X		1																	E-144
0.145 RAMP ART	SAFETY BELTS REQUIRED	1	24	30	5.00						1					X		1																146	
0.158 RAMP ART	ONE WAY	1	36	12	3.00						2					X		2																R6-1L		
0.165 RAMP ART		1	30	30	6.25						1					X		1																R3-2		
WEIGH ST. SB 22.0 0.051 RAMP ART		1	36	36	9.00						2					X		2																W3-1		
0.062 RAMP ART	WRONG WAY	1	36	24	6.00						2					X		2																R5-1a		
0.062 RAMP ALT	WRONG WAY	1	36	24	6.00						2					X		2																R5-1a		
0.082 RAMP ART	DO NOT ENTER	1	30	30	6.25						1					X		1																R5-1		
0.082 RAMP ALT	PROHIBITED	1	30	24	5.00																														E-144
	DO NOT ENTER	1	30	30	6.25						1					X		1															BACK TO BACK	R5-1		
0.112 RAMP ART	STOP	1	30	30	6.25						1					X		1																R1-1		
0.112 RAMP ALT	STOP	1	30	30	6.25						1					X		1																R1-1		
0.123 RAMP ART	$500 FINE THROWING TRASH ON HIGHWAYS AND STREAMS	1	24	30	5.00						1					X		1																	E-144
												FT	FT	FT	FT	FT 240.7	FT		EA.	LB	LB	LB		LB	LB	LB	LB									

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

SUBTOTALS SHEET 72	SF	SF	EA.	SF		FT	FT	LB	EA.	LB	EA.	EA.	LB
	86.50						240.7						

PROJECT NAME: **GUILFORD-ROCKINGHAM**
PROJECT NUMBER: **IMG SIGN(44)**

FILE NAME: **z12A528tssrestarea.xlsb** PLOT DATE: **4/16/2014**
PROJECT LEADER: **C. GREGORY** DRAWN BY: **J. SMITH**
DESIGNED BY: **J. SMITH** CHECKED BY: **D. MUNRO**
TRAFFIC SIGN SUMMARY SHEET 72 SHEET **129** OF **157**