QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

				ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
				69,500	69,500	LB	BITUMINOUS CRACK SEALING (AASHTO M 324 (ASTM D 6690) TYPE IV)	417.10	596
				149,250	149,250	LB	BITUMINOUS CRACK SEALING, "BLOW AND GO" METHOD (AASHTO M 324 (ASTM D 6690) TYPE II)	417.20	196
				1,275	1,275	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST
				3,400	3,400	HR	FLAGGERS	630.15	EST
				1	1	LS	MOBILIZATION/DEMOBILIZATION	635.11	EST
				1	1	LS	TRAFFIC CONTROL	641.10	EST
				6	6	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	EST

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		BITUMINOUS CRACK SEALING (AASHTO M 324 (ASTM D 6690) TYPE IV)
6,700	LB	I-89 NB RANDOLPH - BROOKFIELD
296	LB	I-89 EXIT NB ON RAMP
2,600	LB	I-89 SB SHARON
257	LB	I-89 EXIT 2 SB ON RAMP
196	LB	I-89 EXIT 2 SB OFF RAMP
3,300	LB	I-89 NB MILTON - GEORGIA
166	LB	I-89 EXIT 18 NB OFF RAMP
133	LB	I-89 EXIT 18 NB ON RAMP
8,757	LB	I-91 SB WINDSOR - HARTLAND
171	LB	I-91 EXIT 9 SB OFF RAMP
351	LB	I-91 EXIT 9 SB ON RAMP
4,800	LB	I-91 NB WESTMINSTER - SPRINGFIELD
5,575	LB	I-91 NB NEWBURY
5,575	LB	I-91 SB NEWBURY
152	LB	I-91 EXIT 17 NB OFF RAMP
230	LB	I-91 EXIT 17 NB ON RAMP
223	LB	I-91 EXIT 17 SB ON RAMP
180	LB	I-91 EXIT 17 SB OFF RAMP
7,427	LB	VT 12 WORCESTER - ELMORE
5,663	LB	VT 16 GLOVER - BARTON
2,262	LB	VT 25 TOPSHAM (MM ~~1.638~~ - MM 3.900)
1,280	LB	VT 67A BENNINGTON 0.630
2,617	LB	VT 105 TROY
2,252	LB	VT 105 TROY
6,992	LB	VT 113 CHELSEA - VERSHIRE
749	LB	VT 243 TROY
596	LB	ROUNDING
69,500	LB	TOTAL
		BITUMINOUS CRACK SEALING, "BLOW AND GO" METHOD (AASHTO M 324 (ASTM D 6690) TYPE II)
3,500	LB	I-89 SB ROYALTON - RANDOLPH
9,350	LB	I-89 SB COLCHESTER - GEORGIA
152	LB	I-89 EXIT 17 SB OFF RAMP
191	LB	I-89 EXIT 18 SB ON RAMP
236	LB	I-89 EXIT 18 SB OFF RAMP
12,500	LB	I-91 NB SPRINGFIELD - WINDSOR
223	LB	I-91 EXIT 8 NB OFF RAMP
312	LB	I-91 EXIT 8 NB ON RAMP
15,712	LB	US 2 DANVILLE - ST. JOHNSBURY
528	LB	US 2 MIDDLESEX
4,953	LB	US 7 NEW HAVEN - FERRISBURG
11,869	LB	US 7 POWNAL - BENNINGTON
5,769	LB	US 7 ST. ALBANS TOWN - SWANTON
2,793	LB	US 302 GROTON
6,050	LB	US 302 ORANGE
3,625	LB	VT 3 RUTLAND TOWN - PROCTOR
5,684	LB	VT 11 SPRINGFIELD
5,352	LB	VT 14 WILLIAMSTOWN - BARRE TOWN
2,262	LB	VT 25 CORINTH - TOPSHAM ~~(MM 3.339 - MM 1.638)~~
7,905	LB	VT 62 BERLIN - BARRE CITY
6,989	LB	VT 100 MORETOWN - DUXBURY - MORETOWN
1,150	LB	VT 100C JOHNSON
11,684	LB	VT 102 GUILDHALL - MAIDSTONE
4,437	LB	VT 104 FAIRFAX
15,872	LB	VT 114 BRIGHTON - NORTON
178	LB	VT 147 NORTON
7,366	LB	VT 207 ST. ALBANS - HIGHGATE
1,912	LB	VT 313 ARLINGTON - SUNDERLAND
500	LB	VT 346 POWNAL
196	LB	ROUNDING
149,250	LB	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
(MM 1.309 ~ MM 0.630)		

PROJECT NAME: STATEWIDE

PROJECT NUMBER: STP CRAK(31)

FILE NAME: pl2k558.dgn
PROJECT LEADER: FOWLER
DESIGNED BY: LOCKE
pl2k558qs.i

PLOT DATE: 28-FEB-2014 17:38
DRAWN BY: LOCKE
CHECKED BY: HARRINGTON
SHEET 3 OF 14