

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
		ROADWAY	EROSION CONTROL	BRIDGE NO. 34N	BRIDGE NO. 41N	BRIDGE NO. 42N	BRIDGE NO. 44N	BRIDGE NO. 45N	BRIDGE NO. 41C	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
					58				15	73		CY	COMMON EXCAVATION	203.15				
					58				15	73		CY	EARTH BORROW	203.30				
				1	1	1	1	1	1	6		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
				1						1		LS	STRUCTURAL STEEL (I-91 - BRIDGE NO. 34N)	506.75				
									1	1		LS	STRUCTURAL STEEL (I-91 - BRIDGE NO. 41C)	506.75				
					1					1		LS	STRUCTURAL STEEL (I-91 - BRIDGE NO. 41N)	506.75				
						1				1		LS	STRUCTURAL STEEL (I-91 - BRIDGE NO. 42N)	506.75				
							1			1		LS	STRUCTURAL STEEL (I-91 - BRIDGE NO. 44N)	506.75				
								1		1		LS	STRUCTURAL STEEL (I-91 - BRIDGE NO. 45N)	506.75				
				120	120	120	120	120	120	720		HR	TRUCK-MOUNTED ATTENUATOR	608.45				
					1					1		EACH	ENERGY ABSORPTION ATTENUATOR	621.56				
				321	400	2704	1935	340	2704	8404		LF	TEMPORARY TRAFFIC BARRIER	621.90				
				300	300	300	800	300	300	2300		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
				300	300	300	800	300	300	2300		HR	FLAGGERS	630.15				
		1								1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
				1						1		LS	TRAFFIC CONTROL (I-91 - BRIDGE NO. 34N)	641.10				
									1	1		LS	TRAFFIC CONTROL (I-91 - BRIDGE NO. 41C)	641.10				
					1					1		LS	TRAFFIC CONTROL (I-91 - BRIDGE NO. 41N)	641.10				
						1				1		LS	TRAFFIC CONTROL (I-91 - BRIDGE NO. 42N)	641.10				
							1			1		LS	TRAFFIC CONTROL (I-91 - BRIDGE NO. 44N)	641.10				
								1		1		LS	TRAFFIC CONTROL (I-91 - BRIDGE NO. 45N)	641.10				
				30	30	30	60	30	30	210		DAY	PORTABLE CHANGEABLE MESSAGE SIGN RENTAL	641.17				
				721	375	3079	340	340	3079	7934		LF	6 INCH WHITE LINE	646.214				
				1442	750	6158	680	680	6158	15868		LF	TEMPORARY 6 INCH WHITE LINE, TEMPORARY PAVEMENT MARKING TAPE	646.6211				
				1442	750	6158	680	680	6158	15868		LF	TEMPORARY 6 IN YELLOW LINE, TEMPORARY PAVEMENT MARKING TAPE	646.6311				
						350			400	750		LF	TEMPORARY 12 IN WHITE LINE, TEMPORARY PAVEMENT MARKING TAPE	646.6611				
						16			16	32		LF	TEMPORARY 24 INCH STOP BAR, TEMPORARY PAVEMENT MARKING TAPE	646.6811				
				200	375	200	200	200	1200	2375		SF	PAVEMENT MARKING MASK	646.86				
			1100							1100		SY	GEOTEXTILE FOR SILT FENCE	649.51				
					20				10	30		LB	SEED	651.15				
					10				5	15		LB	FERTILIZER	651.18				
					0.1				0.1	0.2		TON	AGRICULTURAL LIMESTONE	651.20				
					0.1				0.1	0.2		TON	HAY MULCH	651.25				
			2200							2200		SY	TEMPORARY EROSION MATTING	653.20				
		5								5		EACH	SPECIAL PROVISION (CPM SCHEDULE)	900.620				
					1					1		LS	SPECIAL PROVISION (CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES)(I-91-BR. NO. 34N)	900.645				
									1	1		LS	SPECIAL PROVISION (CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES)(I-91-BR. NO. 41C)	900.645				
						1				1		LS	SPECIAL PROVISION (CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES)(I-91-BR. NO. 41N)	900.645				

△ REVISED QUANTITY SHEET TO REMOVE ITEM 634.10 - 10/6/2015

PROJECT NAME: WINDSOR - HARTFORD
PROJECT NUMBER: IM BPNT (13)



FILE NAME: z525457qs.dgn
PROJECT LEADER: G.K.DONINGTON
DESIGNED BY: S.BROWN
qs_l.dgn

PLOT DATE: 25-JUNE-2015
DRAWN BY: S.BROWN
CHECKED BY: R.GAUDREAU
SHEET 5 OF 36