

# QUANTITY SHEET 1

| SUMMARY OF ESTIMATED QUANTITIES |          |                 |                |                |                 |                |                |                 |    | TOTALS      |       | DESCRIPTIONS |   |             |       | DETAILED SUMMARY OF QUANTITIES |      |       |
|---------------------------------|----------|-----------------|----------------|----------------|-----------------|----------------|----------------|-----------------|----|-------------|-------|--------------|---|-------------|-------|--------------------------------|------|-------|
| ROADWAY                         | TRAINING | EROSION CONTROL | BRIDGE NO. 58N | BRIDGE NO. 59N | BRIDGE NO. D62N | BRIDGE NO. 63N | BRIDGE NO. 67N | FULL C.E. ITEMS |    | GRAND TOTAL | FINAL | UNIT         | ITEMS   | ITEM NUMBER | ROUND | QUANTITIES                     | UNIT | ITEMS |
|                                 |          |                 |                |                |                 |                | 50             |                 |    | 50          |       | CY           | COMMON EXCAVATION   | 203.15      |       |                                |      |       |
|                                 |          |                 |                |                |                 |                | 50             |                 |    | 50          |       | CY           | EARTH BORROW  | 203.30      |       |                                |      |       |
|                                 |          |                 | 1              | 1              | 1               | 1              | 1              |                 |    | 5           |       | CY           | TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)  | 204.22      |       |                                |      |       |
|                                 |          |                 | 1              |                |                 |                |                |                 |    | 1           |       | LS           | STRUCTURAL STEEL (I-91 - BRIDGE NO. 58N)  | 506.75      |       |                                |      |       |
|                                 |          |                 |                | 1              |                 |                |                |                 |    | 1           |       | LS           | STRUCTURAL STEEL (I-91 - BRIDGE NO. 59N)  | 506.75      |       |                                |      |       |
|                                 |          |                 |                |                |                 |                | 1              |                 |    | 1           |       | LS           | STRUCTURAL STEEL (I-91 - BRIDGE NO. 63N)  | 506.75      |       |                                |      |       |
|                                 |          |                 |                |                |                 |                |                | 1               |    | 1           |       | LS           | STRUCTURAL STEEL (I-91 - BRIDGE NO. 67N)  | 506.75      |       |                                |      |       |
|                                 |          |                 |                |                | 1               |                |                |                 |    | 1           |       | LS           | STRUCTURAL STEEL (TH3 OVER I-91 - BRIDGE NO. D62N)  | 506.75      |       |                                |      |       |
|                                 |          |                 | 120            | 120            | 120             | 120            | 120            |                 |    | 600         |       | HR           | TRUCK-MOUNTED ATTENUATOR  | 608.45      |       |                                |      |       |
|                                 |          |                 |                |                |                 |                |                |                 | 40 | 40          |       | LF           | REMOVING AND RESETTING FENCE  | 620.50      |       |                                |      |       |
|                                 |          |                 | 540            | 1830           | 1170            | 530            | 1670           |                 |    | 5740        |       | LF           | TEMPORARY TRAFFIC BARRIER   | 621.90      |       |                                |      |       |
|                                 |          |                 | 300            | 300            | 300             | 300            | 300            |                 |    | 1500        |       | HR           | UNIFORMED TRAFFIC OFFICERS  | 630.10      |       |                                |      |       |
|                                 |          |                 | 300            | 300            | 300             | 300            | 300            |                 |    | 1500        |       | HR           | FLAGGERS  | 630.15      |       |                                |      |       |
|                                 |          |                 |                |                |                 |                |                | 1               |    | 1           |       | LS           | FIELD OFFICE, ENGINEERS   | 631.10      |       |                                |      |       |
|                                 |          |                 |                |                |                 |                |                | 1               |    | 1           |       | LS           | TESTING EQUIPMENT, PROTECTIVE COATINGS  | 631.18      |       |                                |      |       |
|                                 |          |                 |                |                |                 |                |                | 3000            |    | 3000        |       | DL           | FIELD OFFICE TELEPHONE (N.A.B.I.)   | 631.26      |       |                                |      |       |
|                                 |          | 540             |                |                |                 |                |                |                 |    | 540         |       | HR           | EMPLOYEE TRAINEESHIP  | 634.10      |       |                                |      |       |
| 1                               |          |                 |                |                |                 |                |                |                 |    | 1           |       | LS           | MOBILIZATION/DEMOBILIZATION   | 635.11      |       |                                |      |       |
|                                 |          |                 | 1              |                |                 |                |                |                 |    | 1           |       | LS           | TRAFFIC CONTROL (I-91 - BRIDGE NO. 58N)   | 641.10      |       |                                |      |       |
|                                 |          |                 |                | 1              |                 |                |                |                 |    | 1           |       | LS           | TRAFFIC CONTROL (I-91 - BRIDGE NO. 59N)   | 641.10      |       |                                |      |       |
|                                 |          |                 |                |                |                 |                | 1              |                 |    | 1           |       | LS           | TRAFFIC CONTROL (I-91 - BRIDGE NO. 63N)   | 641.10      |       |                                |      |       |
|                                 |          |                 |                |                |                 |                |                | 1               |    | 1           |       | LS           | TRAFFIC CONTROL (I-91 - BRIDGE NO. 67N)   | 641.10      |       |                                |      |       |
|                                 |          |                 |                |                |                 |                |                | 1               |    | 1           |       | LS           | TRAFFIC CONTROL (TH3 OVER I-91 - BRIDGE NO. D62N)   | 641.10      |       |                                |      |       |
|                                 |          |                 | 30             | 30             | 30              | 30             | 30             |                 |    | 150         |       | DAY          | PORTABLE CHANGEABLE MESSAGE SIGN RENTAL   | 641.17      |       |                                |      |       |
|                                 |          |                 | 1080           | 2205           | 1545            | 930            | 1620           |                 |    | 7380        |       | LF           | 6 INCH WHITE LINE   | 646.214     |       |                                |      |       |
|                                 |          |                 | 1080           | 2205           | 1545            | 1860           | 1620           |                 |    | 8310        |       | LF           | 6 INCH YELLOW LINE  | 646.215     |       |                                |      |       |
|                                 |          |                 | 1080           |                |                 |                |                |                 |    | 1080        |       | LF           | 12 INCH YELLOW LINE   | 646.25      |       |                                |      |       |
|                                 |          |                 | 2160           | 4410           | 3090            | 1860           | 3240           |                 |    | 14760       |       | LF           | TEMPORARY 6 INCH WHITE LINE, TEMPORARY PAVEMENT MARKING TAPE                                      | 646.6211    |       |                                |      |       |
|                                 |          |                 | 2160           | 4410           | 3090            | 1860           | 3240           |                 |    | 14760       |       | LF           | TEMPORARY 6 IN YELLOW LINE, TEMPORARY PAVEMENT MARKING TAPE                                       | 646.6311    |       |                                |      |       |
|                                 |          |                 |                | 220            |                 |                | 350            |                 |    | 570         |       | LF           | TEMPORARY 12 IN WHITE LINE, TEMPORARY PAVEMENT MARKING TAPE                                       | 646.6611    |       |                                |      |       |
|                                 |          |                 |                | 16             |                 |                | 16             |                 |    | 32          |       | LF           | TEMPORARY 24 INCH STOP BAR, TEMPORARY PAVEMENT MARKING TAPE                                       | 646.6811    |       |                                |      |       |
|                                 |          |                 | 1080           | 600            | 600             | 200            | 600            |                 |    | 3080        |       | SF           | PAVEMENT MARKING MASK   | 646.86      |       |                                |      |       |
|                                 |          | 1100            |                |                |                 |                |                |                 |    | 1100        |       | SY           | GEOTEXTILE FOR SILT FENCE   | 649.51      |       |                                |      |       |
|                                 |          |                 |                |                |                 |                | 20             |                 |    | 20          |       | LB           | SEED  | 651.15      |       |                                |      |       |
|                                 |          |                 |                |                |                 |                | 10             |                 |    | 10          |       | LB           | FERTILIZER  | 651.18      |       |                                |      |       |
|                                 |          |                 |                |                |                 |                | 0.1            |                 |    | 0.1         |       | TON          | AGRICULTURAL LIMESTONE  | 651.20      |       |                                |      |       |
|                                 |          |                 |                |                |                 |                | 0.1            |                 |    | 0.1         |       | TON          | HAY MULCH   | 651.25      |       |                                |      |       |
|                                 |          | 2200            |                |                |                 |                |                |                 |    | 2200        |       | SY           | TEMPORARY EROSION MATTING   | 653.20      |       |                                |      |       |
|                                 |          |                 |                |                |                 |                |                |                 |    | 1           |       | LS           | SPECIAL PROVISION (CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES) (I-91 - BR. NO. 59N) | 900.645     |       |                                |      |       |

PROJECT NAME: BRADFORD-NEWBURY  
 PROJECT NUMBER: IM BPNT (14)  
 FILE NAME: z525458qs.dgn  
 PROJECT LEADER: G.K.DONINGTON  
 DESIGNED BY: S.BROWN  
 MANCHESTER, NH 03101  
 PLOT DATE: 11-AUG-2014  
 DRAWN BY: S.BROWN  
 CHECKED BY: R.GAUDREAU  
 SHEET 6 OF 26

