

QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES										TOTALS			DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES				
										ROADWAY	EROSION CONTROL	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
										1			1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201J0	-			
										1J			1J		ACRE	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201J1	0J			
										300			300		CY	COMMON EXCAVATION	203J5	EST			
										100			100		CY	SOLID ROCK EXCAVATION	203J6	EST			
										1			1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-			
										50			50		TON	AGGREGATE SHOULDERS	402J2	2.6			
										2			2		EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS II	604.415	-			
										502			502		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	-			
										1			1		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-			
										37.5			37.5		LF	REMOVE AND RESET GUARDRAIL	621.75	-			
										14.5			14.5		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	-			
										3500			3500		LF	TEMPORARY TRAFFIC BARRIER	621.90	45			
										240			240		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST			
										40			40		HR	FLAGGERS	630.15	EST			
										20			20		HR	FLAGGERS, RAILROAD	630.20	EST			
												1	1		LS	FIELD OFFICE, ENGINEERS	631J0	-			
												3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-			
										1			1		LS	MOBILIZATION/DEMOBILIZATION	635J1	-			
										1			1		LS	TRAFFIC CONTROL	641J0	-			
										6			6		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641J5	-			
										2			2		EACH	PORTABLE ARROW BOARD	641J6	-			
										6850			6850		LF	TEMPORARY 6 INCH WHITE LINE, TEMPORARY PAVEMENT MARKING TAPE	646.621	35			
										500			500		SF	PAVEMENT MARKING MASK	646.86	52			
										60			60		SY	GEOTEXTILE FOR SILT FENCE	649.51	2.6			
										60			60		LB	SEED	651J5	EST			
										250			250		LB	FERTILIZER	651J8	EST			
										1			1		TON	AGRICULTURAL LIMESTONE	651.20	EST			
										1			1		TON	HAY MULCH	651.25	EST			
										120			120		CY	TOPSOIL	651.35	EST			
										1			1		LS	EPSC PLAN	652.10	-			
										110			110		HR	MONITORING EPSC PLAN	652.20	EST			
										1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30	-			
										2300			2300		SY	TEMPORARY EROSION MATTING	653.20	EST			
										40			40		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25	5			
										70			70		CY	VEHICLE TRACKING PAD	653.35	2			
										8			8		EACH	INLET PROTECTION DEVICE, TYPE I	653.40	-			
										2550			2550		LF	PROJECT DEMARCATION FENCE	653.55	41			
										2			2		EACH	REMOVING SIGNS	675.50	-			
										2			2		EACH	ERECTING SALVAGED SIGNS	675.60	-			
										2			2		EACH	SETTING SALVAGED POSTS	675.61	-			
										7			7		EACH	DELINEATOR WITH STEEL POST	676.10	-			
										6			6		EACH	REMOVAL OF EXISTING DELINEATOR	676.12	-			

PROJECT NAME: RYEGATE	
PROJECT NUMBER: IM 091-2(80)	
FILE NAME: z13a368q+ybdr.dgn	PLOT DATE: 3/30/2017
PROJECT LEADER: D. GOZALKOWSKI	DRAWN BY: J. HEALD
DESIGNED BY: J. OLSEN	CHECKED BY: J. SHIELDS
QUANTITY SHEET 1	SHEET 8 OF 61



FILE NAME: W:\P\c\users\jheald\My Documents\Highway\13a368\Consultants\Highway\13a368q+ybdr.dgn
 DATE/TIME: 3/30/2017
 USER: jheald