COMPOSITE QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

BERLIN-BARRE CITY NH SURF(44)	BERLIN-MONTPELIER IM SURF(45)	HARTFORD-SHARON IM SURF(46)	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
9700	9000	46000	63700	LF	SHOULDER BERM REMOVAL	203.40	1092
1	1	1	3	CY	TRENCH EXCAVATION OF EARTH, EXPLORATION (N.A.B.I.)	204.22	EST
2400	3600	3800	9800	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	496
300	100	400	800	TON	AGGREGATE SHOULDERS	402.12	96
1	1	1	3	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-
1500	500	4500	7000	LB	BITUMINOUS CRACK SEALING, "BLOW AND GO" METHOD (AASHTO M 234 (ASTM D 6690) TYPE II)	417.20	EST
600			600	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	EST
	90	210	300	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG (@ FINGER PLATE/ VERMONT JOINT)	516.10	10
110	135	260	505	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	16
100	100	100	300	CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	EST
10			10	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	EST
30	30	100	160	HR	POWER BROOM RENTAL, TYPE I	608.30	EST
100	100	100	300	HR	TRUCK RENTAL	608.37	EST
200	200	200	600	HR	TRUCK-MOUNTED ATTENUATOR	608.45	EST
100	100	100	300	HR	TRUCK-MOUNTED ATTENUATOR,AWV/PV	608.50	EST
400	400	1000	1800	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST
200	200	300	700	HR	FLAGGERS	630.15	EST
0.33	0.33	0.34	1	LS	FIELD OFFICE, ENGINEERS	631.10	-
0.33	0.33	0.34	1	LS	TESTING EQUIPMENT, BITUMINOUS (N.A.B.I.)	631.17	-
3000	3000	3000	9000	DL	FIELD OFFICE, TELEPHONE (N.A.B.I.)	631.26	-
0.33	0.33	0.34	1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
1			1	LS	TRAFFIC CONTROL (NH SURF (44))	641.10	-
	1		1	LS	TRAFFIC CONTROL (IM SURF(45))	641.10	-
		1	1	LS	TRAFFIC CONTROL (IM SURF(46))	641.10	-
5	2	8	15	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
38000	40000	90000	168000	LF	DURABLE 6 INCH WHITE LINE, POLYUREA	646.424	5091
32000	30000	74000	136000	LF	DURABLE 6 INCH YELLOW LINE, POLYUREA	646.434	2029
	1200	4900	6100	LF	DURABLE 12 INCH WHITE LINE, POLYUREA	646.464	169
40			40	LF	DURABLE 12 INCH YELLOW LINE, POLYUREA	646.474	EST
					BEGIN OPTION AA		
130		35	165	LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	10
130		35	165	LF	DURABLE 24 INCH STOP BAR, POLYUREA	646.484	10
					END OPTION AA		

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: BERLIN-BARRE CITY, BERLIN-MONTPELIER, HARTFORD-SHARON

PROJECT NUMBER: NH SURF (44), IM SURF(45), IM SURF(46)

FILE NAME:13b634/pvtmgt/pl3b634_wrk.dgn PLOT DATE: 06-JUN-2014
PROJECT LEADER: J. HARRINGTON DRAWN BY: PVT. MGT.
DESIGNED BY: PVT. MGT. CHECKED BY: PAVT MGMT
COMPOSITE QUANTITY SHEET 1 SHEET 4 OF 64