

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
						ROADWAY	BRIDGE	FULL CE ITEMS	ALTERNATE A	ALTERNATE B	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
						46000					46000		LF	SHOULDER BERM REMOVAL	203.40	719			COLD PLANING, BITUMINOUS CONCRETE
						1					1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST	289	SY	APPROACHES
						3800					3800		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	134	1867	SY	RAMPS
						400					400		TON	AGGREGATE SHOULDERS	402.12	85	1210	SY	BRIDGE #6N
						1					1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-	222	SY	U-TURNS AND REST AREA RAMPS
						4500					4500		LB	BITUMINOUS CRACK SEALING, "BLOW AND GO" METHOD (AASHTO M 234 (ASTM D 6690) TYPE II)	417.20	EST	212	SY	ROUND
							210				210		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG (@ FINGER PLATE/VERMONT JOINT)	516.10	6	3800	SY	TOTAL
							260				260		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	4			
							100				100		CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	EST			
						100					100		HR	POWER BROOM RENTAL, TYPE I	608.30	EST			
						100					100		HR	TRUCK RENTAL	608.37	EST			
						200					200		HR	TRUCK-MOUNTED ATTENUATOR	608.45	EST			
						100					100		HR	TRUCK-MOUNTED ATTENUATOR, AWW/PV	608.50	EST			
						1000					1000		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST			
						300					300		HR	FLAGGERS	630.15	EST			
								0.34			0.34		LS	FIELD OFFICE, ENGINEERS	631.10	EST			
								0.34			0.34		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-			
								3000			3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	EST			
						0.34					0.34		LS	MOBILIZATION/DEMOBILIZATION	635.11	-			
						1					1		LS	TRAFFIC CONTROL (IM SURF(46))	641.10	-			
						8					8		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-			
						90000					90000		LF	DURABLE 6 INCH WHITE LINE, POLYUREA	646.424	1494			
						74000					74000		LF	DURABLE 6 INCH YELLOW LINE, POLYUREA	646.434	386			
						4900					4900		LF	DURABLE 12 INCH WHITE LINE, POLYUREA	646.464	104			
														BEGIN OPTION AA					
						35					35		LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	2			
						35					35		LF	DURABLE 24 INCH STOP BAR, POLYUREA	646.484	2			
														END OPTION AA					
														BEGIN OPTION BB					
						34					34		EACH	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	-			
						34					34		EACH	DURABLE LETTER OR SYMBOL, POLYUREA	646.494	-			
														END OPTION BB					
						90000					90000		LF	TEMPORARY 6 INCH WHITE LINE, PAINT	646.622	1494			
						74000					74000		LF	TEMPORARY 6 INCH YELLOW LINE, PAINT	646.632	386			
						4900					4900		LF	TEMPORARY 12 INCH WHITE LINE, PAINT	646.662	104			
						35					35		LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	2			
						34					34		EACH	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-			
						4200					4200		EACH	LINE STRIPING TARGETS	646.76	59			
						164					164		LF	PAINTED CURB	646.81	-			
						29					29		SF	PAINTED ISLAND	646.82	-			

PROJECT NAME: HARTFORD-SHARON
PROJECT NUMBER: IM SURF(46)

FILE NAME: I3a638/pvtmg+/p3a638_wrk.dgn PLOT DATE: 06-JUN-2014
PROJECT LEADER: J. HARRINGTON DRAWN BY: PVT. MGT.
DESIGNED BY: PVT. MGT. CHECKED BY: PVT. MGT.
QUANTITY SHEET 1 SHEET 44 OF 64