STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES	TOTALS		DESCRIPTIONS					DETAILED SUMMARY OF QUANTITIES		
ROADWAY	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND		QUANTITIES	UNIT	ITEMS
3600	3600		HR	TRUCK-MOUNTED ATTENUATOR, AWV/PV	608.50	EST.				6 INCH WHITE LINE, WATERBORNE PAINT
2000	2000		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.		4070643	LF	2015*
20	20		HR	FLAGGERS	630.15	EST.		2187590	LF	2015 REAPPLY*
								4357983	LF	2016**
1	1		LS	MOBILIZATION/DEMOBILIZATION	635.11	-		2342008	LF	2016 REAPPLY**
										6 INCH YELLOW LINE, WATERBORNE PAINT
1	1		LS	TRAFFIC CONTROL	641.10	-		3293895	LF	2015*
								1837800	LF	2015 REAPPLY *
4	4		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-		3526405	LF	2016**
								1967527	LF	2016 REAPPLY**
2	2		EACH	PORTABLE ARROW BOARD	641.16	-				
										12 INCH WHITE LINE, WATERBORNE PAINT
12959000	12959000		LF	6 INCH WHITE LINE, WATERBORNE PAINT	646.2141	776		135163	LF	2015*
								151064	LF	2016***
10626000	10626000		LF	6 INCH YELLOW LINE, WATERBORNE PAINT	646.2151	373				
										24 INCH STOP BAR, WATERBORNE PAINT
287000	287000		LF	12 INCH WHITE LINE, WATERBORNE PAINT	646.241	773		3913	LF	2015*
								4374	LF	2016***
8500	8500		LF	24 INCH STOP BAR, WATERBORNE PAINT	646.261	213				
										LETTER OR SYMBOL, WATERBORNE PAINT
4550	4550		EACH	LETTER OR SYMBOL, WATERBORNE PAINT	646.301	10		2144	EA	2015*
								2396	EA	2016***
1200	1200		LF	CROSSWALK MARKING, WATERBORNE PAINT	646.311	75				
										CROSSWALK MARKING, WATERBORNE PAINT
8	8		EACH	RAILROAD CROSSING SYMBOL, WATERBORNE PAINT	646.321	-		531	LF	2015*
								594	LF	2016***
500	500		SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85	EST.				
										THE WORK UNDER THIS CONTRACT SHALL BE COMPLETED
										IN TWO SUCCESSIVE CONSTRUCTION SEASONS. A
										COMPLETE APPLICATION OF MARKINGS, INCLUDING
										REAPPLY AREAS AS SPECIFIED IN THE CONTRACT
										DOCUMENTS AND AS DIRECTED BY THE ENGINEER, SHALL
										BE COMPLETED IN EACH CONSTRUCTION SEASON. REAPPLY
										AREAS WILL BE MAINLINE OF I-89, I-189 AND I-91. SEE THE
										SPECIAL PROVISIONS FOR SPECIFIC CONTRACT
										COMPLETION AND REAPPLY AREA REQUIREMENTS.
										BASED ON ANTICIPATED PAVING SCHEDULES, A FRACTION
										OF THE OVERALL QUANTITY HAS BEEN GAPPED OUT FOR
										EACH YEAR AS NOTED BELOW. UPDATED LOCATIONS
										AND LENGTHS WILL BE PROVIDED AT PRECONSTRUCTION.
										*15% GAP OUT APPLIED
										**9% GAP OUT APPLIED
										***5% GAP OUT APPLIED

PROJECT NAME: STATEWIDE
PROJECT NUMBER: IMG MARK(115)

FILE NAME: t14t185.dgn
PROJECT LEADER: P. COBURN
DESIGNED BY: K. SWEET
QUANTITY SHEET

PLOT DATE: 1/29/2015
DRAWN BY: K. SWEET
CHECKED BY: I. DEGUTIS
SHEET 2 OF 33