QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

ROADWAY (ALT. A)	ROADWAY (ALT. B)	BRIDGE	ROADWAY	FULL C.E.	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
							BEGIN ITEMS COMMON TO ALL ALTERNATES		
			60,700		60,700	LF	SHOULDER BERM REMOVAL	203.40	87
			1		1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-
			350		350	TON	AGGREGATE SHOULDERS, RAP	402.13	EST.
			1		1	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-
			60,000		60,000	LB	BITUMINOUS CRACK SEALING, "BLOW AND GO" METHOD (AASHTO M 324 (ASTM D 6690) TYPE II)	417.20	EST.
		82			82	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	EST.
		100			100	CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	EST.
			200		200	HR	POWER BROOM RENTAL, TYPE I	608.30	EST.
			200		200	HR	POWER BROOM RENTAL, TYPE II	608.31	EST.
			200		200	HR	TRUCK RENTAL	608.37	EST.
			200		200	HR	TRUCK MOUNTED ATTENUATOR	608.45	EST.
			100		100	HR	TRUCK MOUNTED ATTENUATOR, AMV/PV	608.50	EST.
			900		900	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
			500		500	HR	FLAGGERS	630.15	EST.
				1	1	LS	FIELD OFFICE, ENGINEERS	631.10	-
				1	1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
				3,000	3,000	DL	FIELD OFFICE, TELEPHONE (N.A.B.I.)	631.26	-
			1		1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
			1		1	LS	TRAFFIC CONTROL	641.10	-
			4		4	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	EST.
			169,000		169,000	LF	DURABLE 6 INCH WHITE LINE, POLYUREA	646.424	726
			131,000		131,000	LF	DURABLE 6 INCH YELLOW LINE, POLYUREA	646.434	168
			4,500		4,500	LF	DURABLE 12 INCH WHITE LINE, POLYUREA	646.464	90
			160		160	LF	DURABLE 24 INCH STOP BAR, POLYUREA	646.484	10
			30		30	EA	DURABLE LETTER OR SYMBOL, POLYUREA	646.494	-
			169,000		169,000	LF	TEMPORARY 6 INCH WHITE LINE, PAINT	646.622	726
			131,000		131,00	LF	TEMPORARY 6 INCH YELLOW LINE, PAINT	646.632	168
			4,500		4,500	LF	TEMPORARY 12 INCH WHITE LINE, PAINT	646.662	40
			160		160	LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	10
			30		30	EA	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-
			9,900		9,900	EA	LINE STRIPING TARGETS	646.76	133
			1		1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-
			413,600		413,600	SY	SPECIAL PROVISION (MICRO-MILLING BITUMINOUS CONCRETE PAVEMENT)	900.675	132
			100		100	TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE I)	900.680	EST.
							END ITEMS COMMON TO ALL ALTERNATES		

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: BETHEL-BROOKFIELD
PROJECT NUMBER: IM SURF(54)

FILE NAME: pl4v206wrk.dgn
PROJECT LEADER: M. FOWLER
DESIGNED BY: B. KIPP
QUANTITY SHEET 1

PLOT DATE: 2/10/2015
DRAWN BY: B. KIPP
CHECKED BY: M. FOWLER
SHEET 9 OF 22