

# QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES											TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
											GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
											3000	3000	HR	TRUCK-MOUNTED ATTENUATOR, AWW/PV	608.50	EST.			6 INCH WHITE LINE, WATERBORNE PAINT
											2000	2000	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.	4405873	LF	2017*
																	2367744	LF	2017 REAPPLY*
																	4070643	LF	2018**
											20	20	HR	FLAGGERS	630.15	EST.	2187590	LF	2018 REAPPLY**
																	13031850	LF	SUBTOTAL
											1	1	LS	TRAFFIC CONTROL	641.10	-	150	LF	ROUNDING
																	13032000	LF	TOTAL
											4	4	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-			6 INCH YELLOW LINE, WATERBORNE PAINT
																	3565156	LF	2017*
											2	2	EACH	PORTABLE ARROW BOARD	641.16	-	1989149	LF	2017 REAPPLY*
											13032000	13032000	LF	6 INCH WHITE LINE, WATERBORNE PAINT	646.2141	150	3293895	LF	2018**
											10686000	10686000	LF	6 INCH YELLOW LINE, WATERBORNE PAINT	646.2151	-	1837800	LF	2018 REAPPLY**
																	10686000	LF	SUBTOTAL
											285000	285000	LF	12 INCH WHITE LINE, WATERBORNE PAINT	646.241	264	0	LF	ROUNDING
											8700	8700	LF	24 INCH STOP BAR, WATERBORNE PAINT	646.261	90	10686000	LF	TOTAL
											4750	4750	EACH	LETTER OR SYMBOL, WATERBORNE PAINT	646.301	14			12 INCH WHITE LINE, WATERBORNE PAINT
																	140084	LF	2017*
											1200	1200	LF	CROSSWALK MARKING, WATERBORNE PAINT	646.311	31	144652	LF	2018***
																	284736	LF	SUBTOTAL
											8	8	EACH	RAILROAD CROSSING SYMBOL, WATERBORNE PAINT	646.321	-	264	LF	ROUNDING
																	285000	LF	TOTAL
											500	500	SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85	EST.			24 INCH STOP BAR, WATERBORNE PAINT
																	4236	LF	2017*
											1	1	LS	SPECIAL PROVISION (MOBILIZATION/DEMOBILIZATION)	900.645	-	4374	LF	2018***
																	8610	LF	SUBTOTAL
																	90	LF	ROUNDING
																	8700	LF	TOTAL
																			LETTER OR SYMBOL, WATERBORNE PAINT
																	2330	LF	2017*
																	2406	LF	2018***
																	4736	LF	SUBTOTAL
																	14	LF	ROUNDING
																	4750	LF	TOTAL
																			CROSSWALK MARKING, WATERBORNE PAINT
																	575	LF	2017*
																	594	LF	2018***
																	1169	LF	SUBTOTAL
																	31	LF	ROUNDING
																	1200	LF	TOTAL

THE WORK UNDER THIS CONTRACT SHALL BE COMPLETED IN TWO SUCCESSIVE CONSTRUCTION SEASONS. A COMPLETE APPLICATION OF MARKINGS, INCLUDING REAPPLY AREAS AS SPECIFIED IN THE CONTRACT DOCUMENTS AND AS DIRECTED BY THE ENGINEER, SHALL BE COMPLETED IN EACH CONSTRUCTION SEASON. REAPPLY AREAS WILL BE MAINLINE OF I-89, I-189, AND I-91 SEE THE SPECIAL PROVISIONS FOR SPECIFIC CONTRACT COMPLETION AND REQUIREMENTS REAPPLY AREA

BASED ON ANTICIPATED PAVING SCHEDULES, A FRACTION OF THE OVERALL QUANTITY HAS BEEN GAPPED OUT FOR EACH YEAR AS NOTED BELOW. UPDATED LOCATIONS AND LENGTHS WILL BE PROVIDED AT PRECONSTRUCTION

\*8% GAP OUT APPLIED  
\*\*15% GAP OUT APPLIED  
\*\*\*5% GAP OUT APPLIED

PROJECT NAME: STATEWIDE  
PROJECT NUMBER: IMG MARK(116)

FILE NAME: z16+084.dgn PLOT DATE: 1/23/2017  
PROJECT LEADER: C. LATHROP DRAWN BY: P. DAY  
DESIGNED BY: P. DAY CHECKED BY: C. LATHROP  
QUANTITY SHEET SHEET 2 OF 34