INDEX OF SHEETS

INDEX OF SHEETS

1. TITLE SHEET
2. INDEX OF SHEETS
3. CONVENTIONAL SYMBOLOGY SHEET
4.-5. TYPICAL SECTION SHEETS
6.-7. QUANTITY SHEETS
8. PROJECT NOTES
9. DETAIL SHEET
10. PAVEMENT MARKING DETAIL SHEET
11. MICROMILLING DETAIL SHEET
12. INLAY DETAIL SHEET
13. TYPICAL INTERCHANGE CONSTRUCTION DETAIL SHEET
14.-23. BRIDGE DETAIL SHEETS
24. VT JOINT ASPHALTIC PLUG DETAIL SHEET
25. FINGER JOINT ASPHALTIC PLUG DETAIL SHEET
26.-39. PLAN SHEETS
40. REST AREA DETAIL SHEET 1
41. REST AREA DETAIL SHEET 2
42.-43. TRAFFIC SIGNAL PLAN SHEETS
44. SIGN DETAIL SHEET
45.-49. CONSTRUCTION APPROACH SIGNING SHEETS
50. CONSTRUCTION APPROACH SIGNING SHEET NOTES
51. RUTTING DATA INFORMATION SHEET NB
52. ROUGHNESS DATA INFORMATION SHEET NB
53. RUTTING DATA INFORMATION SHEET SB
54. ROUGHNESS DATA INFORMATION SHEET SB

VAOT DESIGN STANDARDS

E-191	02-01-99
E-192	10-12-00
E-193	08-18-95
T-1	04-25-16
T-10	08-06-12
T-11	08-06-12
T-12	08-06-12
T-16	08-06-12
T-17	08-06-12
T-22	08-06-12
T-23	08-06-12
T-28	08-06-12
T-29	08-06-12
T-30	08-06-12
T-31	08-06-12
T-33	08-06-12
T-36	08-06-12

STRUCTURES DETAIL SHEETS

SD-516.10 - BRIDGE JOINT ASPHALTIC PLUG 08-29-11

TRAFFIC DATA

	AADT		DHV		%T		%D		ADTT		ESALs	
	2017	2037	2017	2037	2017	2037	2017	2037	2017	2037	(2017~2037)	(2017~2057)
NORTHBOUND (MM 91.880 - MM 97.870)	15,600	17,500	2400	2700	6.4	11.1	100	100	1400	2700	10,587,000	26,252,000
SOUTHBOUND (MM 91.880 - MM 97.870)	15,600	17,500	2900	3200	4.8	8.3	100	100	1300	2600	10,245,000	25,386,000
NORTHBOUND (MM 97.870 - MM 106.550)	11,300	12,700	1800	2000	7.2	12.8	100	100	1500	2900	11,225,000	27,892,000
SOUTHBOUND (MM 97.870 - MM 106.550)	11,300	12,700	2100	2300	7.4	12.9	100	100	1400	2700	9,034,000	22,355,000
NORTHBOUND (MM 106.550 - MM 113.750)	10,800	12,000	1600	1700	7.4	11.2	100	100	1400	2300	7,805,000	18,122,000
SOUTHBOUND (MM 106.550 - MM 113.750)	10,800	12,000	1600	1800	7.4	11.6	100	100	1400	2400	7,912,000	18,429,000
NORTHBOUND (MM 113.750 - MM 117.630)	6,500	7,200	870	960	9.3	15.9	100	100	930	1800	9,712,000	24,184,000
SOUTHBOUND (MM 113.750 - MM 117.630)	6,500	7,200	730	810	9.9	16.8	100	100	910	1700	7,628,000	18,811,000
NORTHBOUND (MM 117.630 - MM 118.200)	5,100	5,700	680	760	10.3	15.3	100	100	800	1300	6,153,000	14,434,000
SOUTHBOUND (MM 117.630 - MM 118.200)	5,100	5,700	570	640	13.0	20.2	100	100	770	1300	4,559,000	10,670,000

PROJECT NAME: COLCHESTER-SWANTON
PROJECT NUMBER: IM SURF(56)

FILE NAME: pl6v07lwrk.dgn
PROJECT LEADER: M. FOWLER
DESIGNED BY: B. KIPP
INDEX OF SHEETS

PLOT DATE: 29-DEC-2016
DRAWN BY: B. KIPP
CHECKED BY: M. FOWLER
SHEET 2 OF 54