

# QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	TRAINING	BRIDGE	FULL C.E.	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							50000				50000		LF	SHOULDER BERM REMOVAL	203.40	EST.			U-TURNS
							1				1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-	4650	SY	COLD PLANING, BITUMINOUS PAVEMENT
							4650				4650		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	11	40	CWT	EMULSIFIED ASPHALT
														BEGIN OPTION AA			410	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
							700				700		TON	AGGREGATE SHOULDERS	402.12	EST.	344	SY	MICRO-MILLING
							700				700		TON	AGGREGATE SHOULDERS, RAP	402.13	EST.	344	SY	PAVER-PLACED SURFACE TREATMENT, TYPE C
														END OPTION AA					
							40				40		CWT	EMULSIFIED ASPHALT	404.65	EST.			
							1				1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-			
							52000				52000		LB	BITUMINOUS CRACK SEALING, "BLOW AND GO" METHOD	417.20	EST.			
							410				410		TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	4			
									410		410		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG (@ FINGER/VERMONT JOINT)	516.10	EST.			
									1850		1850		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	EST.			
									100		100		CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	EST.			
							12				12		EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	-			
							200				200		HR	POWER BROOM RENTAL, TYPE I	608.30	EST.			
							200				200		HR	POWER BROOM RENTAL, TYPE II	608.31	EST.			
							200				200		HR	TRUCK RENTAL	608.37	EST.			
							200				200		HR	TRUCK-MOUNTED ATTENUATOR	608.45	EST.			
							100				100		HR	TRUCK-MOUNTED ATTENUATOR, AWW/PV	608.50	EST.			
							2000				2000		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.			
							1000				1000		HR	FLAGGERS	630.15	EST.			
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10	-			
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-			
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-			
								520			520		HR	EMPLOYEE TRAINEESHIP	634.10	-			
							1				1		LS	MOBILIZATION/DEMOBILIZATION	635.11	-			
							1				1		LS	TRAFFIC CONTROL	641.10	-			
							9				9		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-			
							382500				382500		LF	TEMPORARY 6 INCH WHITE LINE, PAINT	646.622	326			
							296000				296000		LF	TEMPORARY 6 INCH YELLOW LINE, PAINT	646.632	56			
							7200				7200		LF	TEMPORARY 12 INCH WHITE LINE, PAINT	646.662	35			
							200				200		LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	9			
							108				108		EACH	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-			
							36500				36500		EACH	LINE STRIPING TARGETS	646.76	91			
							130				130		SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85	EST.			
							1				1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-			
							5				5		EACH	SPECIAL PROVISION (CPM SCHEDULE)	900.620	-			

PROJECT NAME: COLCHESTER-SWANTON  
PROJECT NUMBER: IM SURF(56)  
FILE NAME: pl6v07l\_wrk.dgn PLOT DATE: 22-DEC-2016  
PROJECT LEADER: M. FOWLER DRAWN BY: B. KIPP  
DESIGNED BY: B. KIPP CHECKED BY: M. FOWLER  
QUANTITY SHEET 1 SHEET 6 OF 54