QUANTITY SHEET

STATE OF VERMONT AGENCY OF TRANSPORTATION

PROJECT NO. _____

SUMMARY SHEET NO. ____ OF ____ 19 ____

ROUNDING

APPROXIMATE SUMMARY OF QUANTITIES

TEMP EROSION CONTROL	EROSION CONTROL	NON-FEDERAL PARTICIPATION	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.
				560	560	LF	PAINTED CURBS	646.21
				10135	10135	LF	TEMPORARY 4" REFLECTORIZED WHITE LINES	646.35
				6495	6495	LF	TEMPORARY 4" REFLECTORIZED YELLOW LINES	646.36
				450	450	LF	DURABLE 4" REFLECTORIZED WHITE LINES	646.60
				2555	2555	LF	DURABLE 4" REFLECTORIZED YELLOW LINES	646.61
				120	120	LF	DURABLE 24" STOP BAR	646.64
				7	7	EA	DURABLE ARROW MARKINGS	646.65
				44	44	EA	DURABLE LETTER IN WORD MARKINGS	646.66
	660				660	LB	SEED	651.10
60					60	LB	SEED - WINTER RYE	651.12
500	5,500				6000	LB	FERTILIZER	651.15
	22				22	TON	AGRICULTURAL LIMESTONE	651.20
6	22				28	TON	HAY MULCH	651.25
	1100				1100	CY	TOPSOIL	653.10
100	800				900	SY	EROSION MATTING	654.20
200					200	LF	SILT FENCE	654.30
				360	360	SF	TRAFFIC SIGNS, TYPE A	675.20
				1660	1660	LB	TRAFFIC SIGN POSTS, TYPE A	675.35
				70	70	LB	TRAFFIC SIGN POSTS, TYPE C	675.37
				12	12	EA	REMOVING SIGNS	675.53
				1	1	EA	FLASHING BEACON	678.16

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

TYPE OF CONSTRUCTION

STATIONS FROM	STATIONS TO	PAVEMENT WIDTHS			EQUATIONS +	EQUATIONS −	
TOTALS							

LENGTH OF PROJECT

STATIONS	FEET	MILES	REMARKS
TOTALS			

ST. JOHNSBURY DP FF 041-1 (10)

No. Sheet 8 of 229 Filed Sheets

D-1