TRAFFIC SIGN SUMMARY SHEET-TYPE A SIGNS

MILEMARKER, STATION OR SIGN NUMBER	LEGEND	TYPE	SIGN DIMENSIONS	EXISTING SIGNS TO BE SALVAGED: REMOVE (S.F.)	EXISTING SIGNS TO BE SALVAGED: RETAIN (X)	NEW AND SALVAGED SIGNS (S.F.): NEW "A"	NEW AND SALVAGED SIGNS (S.F.): SALVAGED "A"	NEW AND SALVAGED SIGNS (S.F.): NEW "B"	NEW AND SALVAGED SIGNS (S.F.): SALV. "B"	EXISTING POSTS: RETAIN	EXISTING POSTS: DRILL	EXISTING POSTS: SALV.	NEW POSTS: NUMBER OF POSTS	NEW POSTS: TYPE "A" (FLANGED CHANNEL) 2.0 LB./FT.	NEW POSTS: TYPE "A" (FLANGED CHANNEL) 2.5 LB/FT.	NEW POSTS: TYPE "A" (FLANGED CHANNEL) 3.0 LB/FT.	NEW POSTS: TYPE "C" (ALUMINUM) 3" Ø	NEW POSTS: TYPE "C" (ALUMINUM) 3" □	NEW POSTS: TYPE "C" (ALUMINUM) 4" Ø MOD.	NEW POSTS: TYPE "C" (ALUMINUM) 4" Ø	NEW POSTS: TYPE "B" BR'KAWAY STEEL	REMARKS	FOR SIGN DETAIL SEE SHEET OR STANDARD SHEET NUMBER
1-1	TO	A	2' x 1'			2																	
1-2	91	A	2' x 2'			4							1		X								E-11
1-3	↰	A	21" x 15"			2.2																	E-11
																							E-11
2	LEFT LANE MUST TURN LEFT	A	30" x 30"			6.3							1	X									
																							E-15
3-1	← NEWPORT 41	A	72" x 10"			5							2			X							
3-2	← WHITE RIVER JCT. 65	A	72" x 10"			5																	E-23
3-3	H	A	2' x 2'			4																	E-23
3-4	→	A	24" x 6"			1																	E-14
* SEE BELOW FOR -5 & -6																							
4	ST. JOHNSBURY 1	A	72" x 10"			5							2	X									E-14
5-1 (EXISTING)	H	A		X						REMOVE													E-23
5-2	HOSPITAL	A		X																			
5-3	→	A		X																			
6-1	TO	A	2' x 1'			2																	
6-2	91	A	2' x 2'			4							1			X							E-11
6-3	←	A	21" x 15"			2.2																	E-11
7-1	SOUTH	A	2' x 1'			2																	E-11
7-2	5	A	2' x 2'			4							1	X									E-12
7-3	TO	A	2' x 1'			2																	E-12
7-4	2	A	2' x 2'			4							1	X									E-12
																							E-12
8	STOP	A	3' x 3'			9							1			X							E-15C
9-1	NORTH	A	2' x 1'			2																	
9-2	5	A	2' x 2'			4							2				X						E-12
9-3	←	A	21" x 15"			2.2																	E-12
9-4	SOUTH	A	2' x 1'			2																	E-12
9-5	5	A	2' x 2'			4																	E-12
9-6	→	A	21" x 15"			2.2																	E-12
9-7	TO	A	2' x 1'			2																	E-12
9-8	2	A	2' x 2'			4																	E-12
9-9	→	A	21" x 15"			2.2																	E-12
9-10	SERVICES →	A	36" x 7½"			1.9																	E-12
9-11	H	A	2' x 2'			4																	SHEET #53
9-12	↑	A	21" x 15"			2.2																	E-14B
10-1	TO	A	2' x 1'			2							1	X									E-11
10-2	91	A	2' x 2'			4																	E-11
11-1 (EXISTING)	H	A		X						REMOVE													E-11
11-2	←	A		X																			
* CONT. FROM ABOVE 3-5	91	A	2' x 2'			4																	
3-6	←	A	21" x 15"			2.2																	E-11
																							E-11
TOTALS				5		108.6																	

POST LENGTHS ARE APPROXIMATE. FINAL LENGTHS TO BE DETERMINED IN THE FIELD IF FINAL LENGTHS VARY BY MORE THAN 2 FEET, RECOMPUTE THE POST SIZE BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS.

PREPARED BY _____ DATE _____
CHECKED BY _____ DATE _____

ST. JOHNSBURY
PROJ. DP FF NO. 041-1(10)
SHEET 50 OF 229