TRAFFIC SIGN SUMMARY SHEET-TYPE A SIGNS

MILEMARKER, STATION OR SIGN NUMBER	LEGEND	TYPE	SIGN DIMENSIONS	EXISTING SIGNS TO BE SALVAGED: REMOVE (S.F.)	↓	RETAIN (X)	NEW AND SALVAGED SIGNS (S.F.): NEW "A"	SALVAGED "A"	NEW "B"	SALV. "B"	EXISTING POSTS: RETAIN	DRILL	SALV.	NEW POSTS: NUMBER OF POSTS	TYPE "A" (FLANGED CHANNEL): 2.0 LB./FT.	2.5 LB/FT.	3.0 LB/FT.	TYPE "C" (ALUMINUM): 3" Ø	3" □	4" Ø MOD.	4" Ø	TYPE "B" BR'KAWAY STEEL	REMARKS	FOR SIGN DETAIL SEE SHEET OR STANDARD SHEET NUMBER
25-1		A	3' x 3'				9							1		X								E-19
25-2	800 FEET	A	18" x 18"				2.3																	E-19B
26	BRIDGE FREEZE BEFORE ROAD	A	4' x 4'				16							2			X							E-19
27	STOP	A	30" x 30"				6.3							1		X								E-15C
28 (28A & 28B - SEE SHEET # 53)	LEGAL LOAD LIMIT 24000 POUNDS	A	2' x 2'				4							1	X									E-15A
29	←	A	4' x 2'				8							2	X									SHEET # 53 & STD E-19A
30	←	A	4' x 2'				8							2	X									(FOR COLOR & MATERIAL)
31	←	A	4' x 2'				8							2	X									
32-1	Y	A	30" x 30"				6.3							1			X							SHEET # 53 & STD E-19A
32-2	40 MPH	A	18" x 18"				2.3																	E-19B
33-1			3' x 3'				9							1			X						NUMERAL - 6" D	E-19B
33-2	2600 FEET		24" x 18"				3																	E-21
34-1	STOP	A	30" x 30"				6.3							1	X									E-15C
34-2	LEGAL LOAD LIMIT 16000 POUNDS	A	2' x 2'				4																	E-15
35	1½ MILE WINDING ROAD	A		X							REMOVE													
36-1	7%	A	3' x 3'				9							2	X								NUMERAL - 6" D MOUNT 200' EASTERLY OF REVERSE CURVE WARNING SIGN ON T.H. # 9 BEYOND END OF PROJECT	E-19B
36-2	TRUCKS USE LOWER GEAR	A	24" x 18"				3																	SHEET # 53 & STD E-19A (FOR COLOR & MATERIAL)
37	ST. JOHNSBURY 2	A	72" x 10"				5							—									MOUNT ON EXISTING "TO US 5 ↑, TO US 2" ASSEMBLY EASTERLY OF I 91 N.B. OFF-RAMP TERMINAL ON T.H. # 9	
38-1	STATE HIGHWAY BRIDGE	A		X							REMOVE													
38-2	LEGAL LOAD SIGN	A		X																				
39	SPEED LIMIT 30	A		X							REMOVE													
40 SEE NEXT SHEET FOR 41 & 42	SPEED LIMIT 30	A		X							REMOVE													
THE FOLLOWING SIGNS ARE LOCATED OFF PROJECT AS NOTED AND ARE TO BE REMOVED OR REPLACED WITH NEW AS INDICATED. THIS WORK IS NOT A PART OF PROJECT DP FF 041-1(10) AND WILL BE PERFORMED BY STATE FORCES																								
U.S. 5 NB (SOUTH OF PROJ.)	(A) HOSPITAL ENTRANCE 1000 FEET	A	NOT INCL. IN TOT. →	[X]																				
U.S. 5 SB (NORTH OF PROJ.)	(B) HOSPITAL ENTRANCE 1200 FEET	A	" " " "	[X]																				
U.S. 5 N.B. (NORTH OF PROJ.)	(C), (D), (E) TO (91) 3 ASSEMBLIES NORTH OF PROJ. ON U.S. 5	A A	" " " "	[X (3)]							REMOVE (3)													
I-91 @ BEGIN. OF N.B. & S.B. DECELS. (2 SIGNS)	(F) (G) TRUCKS OVER 24000 LBS. PROHIBITED THIS EXIT LEGALLY ENFORCED	B	" " " "	[X (2)]																				
I-91 @ N.B. & S.B. OFF-RAMP GORES (2 SIGNS)	(H) (I) TRUCKS OVER 24000 LBS. PROHIBITED THIS EXIT	B	" " " "	[X (2)]																				
NON-PROJECT SIGNING BY STATE FORCES CONTINUED ON NEXT SHEET. TOTALS				5			109.5																	

POST LENGTHS ARE APPROXIMATE. FINAL LENGTHS TO BE DETERMINED IN THE FIELD IF FINAL LENGTHS VARY BY MORE THAN 2 FEET, RECOMPUTE THE POST SIZE BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS.

PREPARED BY _____ DATE _____
CHECKED BY _____ DATE _____

ST. JOHNSBURY
PROJ. DP FF NO. 041-1(10)