TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	LEGEND	TYPE	SIGN DIMENSIONS	EXISTING SIGNS TO BE SALVAGED: REMOVE (EA.)	EXISTING SIGNS TO BE SALVAGED: RETAIN (X)	NEW AND SALVAGED SIGNS (S.F.): NEW "A"	NEW AND SALVAGED SIGNS (S.F.): SALVAGED "A"	NEW AND SALVAGED SIGNS (S.F.): NEW "B"	NEW AND SALVAGED SIGNS (S.F.): SALV. "B"	EXISTING POSTS: RETAIN	EXISTING POSTS: DRILL	EXISTING POSTS: SALV.	NEW POSTS: NUMBER OF POSTS	NEW POSTS: TYPE "A" (FLANGED CHANNEL) 2.0 LB/FT	NEW POSTS: TYPE "A" (FLANGED CHANNEL) 2.5 LB/FT	NEW POSTS: TYPE "A" (FLANGED CHANNEL) 3.0 LB/FT	NEW POSTS: TYPE "C" (ALUMINUM) 3" ∅	NEW POSTS: TYPE "C" (ALUMINUM) 3" □	NEW POSTS: TYPE "C" (ALUMINUM) 4" ∅	NEW POSTS: TYPE "C" (ALUMINUM) 4" ∅ MOD.	NEW POSTS: TYPE "B" (BREAKAWAY) POST SIZE	NEW POSTS: TYPE "B" (BREAKAWAY) WEIGHT	NEW POSTS: TYPE "B" (BREAKAWAY) FTG. SIZE 24"	NEW POSTS: TYPE "B" (BREAKAWAY) FTG. SIZE 30"	REMARKS	FOR SIGN DETAIL SEE: PLAN SHEET NUMBER	FOR SIGN DETAIL SEE: STD. SHEET NUMBER
8.70 N.B. LT. & RT.		A		X																							
				X																							
8.95 N.B.RT.	(EXIST.) STORM SIGN / (NEW) STORM SIGN	A		X						X																	
			4' x 4'			16																			MOUNT NEW SIGN ON RETAINED POST		E-19
9.00 N.B.RT.	NORTH	A			X					X																	
	89 (HIGH INTENSITY)	A	3' x 3'	X		9																			REMOVE EXISTING SHIELD AND MOUNT NEW SHIELD ON RETAINED POST		E-14
9.25 N.B. RT.	SPEED LIMIT 55	A	4' x 5'	X		20				X (2)															MOUNT NEW SIGNS ON RETAINED POSTS		E-15B
	MINIMUM 40	A	4' x 4'	X		16																					E-15B
9.30 S.B.LT.	FOOD - PHONE GAS - LODGING STATE POLICE NEXT RIGHT	B		X																							
9.45 N.B.RT. (EXIST.)	WATERBURY 5 BURLINGTON 32	B		X						X															MOUNT NEW SIGN ON EXISTING POSTS -DETAIL SIMILAR TO SIGN M.M. 63.05 S.B.LT.	SHT. #13	
" " " (NEW)								90																			
9.95 S.B.LT.	2 100B MIDDLESEX MORETOWN EXIT 1 MILE	B		X						X		X (T-BARS)															
																									SALVAGE T-BAR ASSEMBLY FOR MOUNTING NEW SIGN		
	NEXT EXIT 7 MILES	B		X																					MOUNT ON NEW T-BAR ASSEMBLY OVER NEW PARENT SIGN		E-14
	EXIT 10 *	B	10' x 2.5'					25						THIS SIGN TO BE FABRICATED WITH 3M HIGH INTENSITY ENCAPSULATED LENS SHEETING FOR TEXT, BACKGROUND AND BORDER.													
	2 TO 100B MIDDLESEX MORETOWN EXIT 1 MILE *	B	16' x 11'					176						THIS SIGN TO BE FABRICATED UNDER A CATEGORY II WORKPLAN- SEE NOTE ON SHEET 10 AND SPECIAL PROVISIONS												MOUNT NEW SIGN ON EXISTING POSTS	SHT. #10	
	NEXT EXIT 7 MILES *	B	13.5' x 2'					27						THIS SIGN TO BE FABRICATED WITH 3M HIGH INTENSITY ENCAPSULATED LENS SHEETING FOR TEXT, BACKGROUND AND BORDER.											MOUNT ON SALVAGED T-BARS		E-14
2.90 N.B.RT.	ENTERING TOWN OF WATERBURY	A	3' x 2'			6							1	X													E-14
2.80 S.B.LT.	ENTERING MIDDLESEX (EXIST.) / (NEW) ENTERING TOWN OF MIDDLESEX	A		X																							
			3' x 2'			6							1	X													E-14
2.15 N.B.RT.	2 100 WATERBURY STOWE EXIT 1 MILE	B		X						X																	
												X (T-BARS)													SALVAGE T-BAR ASSEMBLY FOR MOUNTING NEW SIGN		
	NEXT EXIT 15 MILES	B		X																					MOUNT SIGN ON NEW T-BAR ASSEMBLY OVER NEW PARENT SIGN		E-14
	EXIT 10 *	B	10' x 2.5'					25						THIS SIGN TO BE FABRICATED WITH 3M HIGH INTENSITY ENCAPSULATED LENS SHEETING FOR TEXT, BACKGROUND AND BORDER.													
	100 TO 2 WATERBURY STOWE EXIT 1 MILE *	B	16' x 11'					176						THIS SIGN TO BE FABRICATED UNDER A CATEGORY II WORKPLAN- SEE NOTE ON SHEET 10 AND SPECIAL PROVISIONS											MOUNT NEW SIGN ON EXISTING POSTS	SHT. #10	
	NEXT EXIT 15 MILES *	B	13.5 x 2'					27						THIS SIGN TO BE FABRICATED WITH 3M HIGH INTENSITY ENCAPSULATED LENS SHEETING FOR TEXT, BACKGROUND AND BORDER											MOUNT NEW SIGN ON SALVAGED T-BARS		E-14
2.90 N.B.RT.	BOLTON NEXT RIGHT *	B		X						X																	
			10' x 5'					50																	MOUNT NEW SIGN ON EXISTING POSTS	SHT #13	
3.05 S.B.LT.	MIDDLESEX 3 MONTPELIER 11 *	B		X						X																	
			15' x 5'					75																	MOUNT NEW SIGN ON EXISTING POSTS	SHT #13	
3.10 N.B. RT.	FOOD - PHONE GAS - LODGING CAMPING	B		X																							
3.25 N.B. RT.	BRIDGES FREEZE BEFORE ROADS	A	4' x 4'	X		16				X (2)															MOUNT NEW SIGN ON EXISTING POSTS		E-19
3.30 S.B.LT.	SPEED LIMIT 55	A	4' x 5'	X		20				X (2)															MOUNT NEW SIGN ON EXISTING POSTS		E-15B
	MINIMUM 40	A	4' x 4'	X		16																					E-15B
3.31 N.B. RT.	EXIT 10 *	B	10' x 2.5'					25																			E-14
	2 100 (100) TO Waterbury Stowe (2) RIGHT LANE	B			X					X															RETAIN EXISTING SIGN, REMOVE EXISTING ROUTE SHIELDS AND REPLACE WITH "(100) TO (2)". ADD "EXIT 10" PANEL ON T-BARS ON TOP OF SIGN. ADD SERVICE SYMBOLS BENEATH SIGN ON T-BAR ASSEMBLY. PARENT SIGN MAY HAVE TO BE RAISED TO MAINTAIN CLEARANCES. DO NOT MOUNT SIGNS TO INTERFERE WITH BREAK-A-WAY.		E-13
			(100) 46" x 36"			11.5																					E-12
			(2) 3' x 3'			9																					
		A	30" x 30"			6.3																	E-14B				
		A	30" x 30"			6.3																	E-14B				
TOTALS				19		158.1		696						64													

* SPECIAL NOTE: MODIFICATION OF STANDARD E-14 - PLYWOOD AND ACRYLIC PLASTIC REFLECTORS WILL NOT BE ALLOWED ON TYPE "B" SIGNS

POST LENGTHS ARE APPROXIMATE. FINAL LENGTHS TO BE DETERMINED IN THE FIELD IF FINAL LENGTHS VARY BY MORE THAN 2 FEET, RECOMPUTE THE POST SIZE BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS.

PREPARED BY _____ DATE _____

CHECKED BY _____ DATE _____

MIDDLESEX - WATERBURY

PROJ. IR NO. 089-2(6)

SHEET 11 OF 34