

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
								ROADWAY	EROSION CONTROL	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								21			21		EACH	THINNING AND TRIMMING FOR SIGNS	201.31	EST.			
								225			225		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	-			
								1			1		EACH	MANUFACTURED TERMINAL SECTION, FLARED	621.50	-			
								40			40		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	-			
								875			875		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.			
								175			175		HR	FLAGGERS	630.15	EST.			
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10	-			
										1	1		LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25	-			
								1			1		LS	MOBILIZATION/DEMobilIZATION	635.11	-			
								1			1		LS	TRAFFIC CONTROL	641.10	-			
								4			4		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-			
								2			2		EACH	PORTABLE ARROW BOARD	641.16	-			
									9		9		LB	SEED	651.15	-			
									80		80		LB	FERTILIZER	651.18	9			
									1		1		TON	AGRICULTURAL LIMESTONE	651.20	0.7			
									1		1		TON	HAY MULCH	651.25	0.7			
									80		80		CY	TOPSOIL	651.35	3			
								8011			8011		SF	TRAFFIC SIGNS, TYPE A	675.20	0.18			
								10422			10422		SF	TRAFFIC SIGNS, TYPE B	675.21	0.25			
								45451			45451		LB	W-SHAPE STEEL SIGN POST	675.31	-			
								1610			1610		LB	TUBULAR ALUMINUM SIGN POST	675.32	-			
								45482			45482		LB	TUBULAR STEEL SIGN POST	675.33	0.7			
								9770			9770		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	0.2			
								78			78		EACH	FOUNDATION FOR W-SHAPE STEEL POST, 24 INCH DIAMETER	675.41	-			
								390			390		EACH	FOUNDATION FOR TUBULAR STEEL POST	675.43	-			
								1309			1309		EACH	REMOVING SIGNS (TYPE A)	675.50	-			
								143			143		EACH	REMOVING SIGNS (TYPE B)	675.50	-			
								5			5		EACH	ERECTING SALVAGED SIGNS	675.60	-			
								3300			3300		EACH	DELINEATOR WITH STEEL POST	676.10	EST.			
								3675			3675		EACH	REMOVAL OF EXISTING DELINEATOR	676.12	EST.			
								30			30		EACH	SPECIAL PROVISION (FOUNDATION FOR W-SHAPE STEEL POST, 24 INCH DIAMETER)	900.620	-			

PROJECT NAME: LYNDON - DERBY
 PROJECT NUMBER: IM IR 091-3(6)
 FILE NAME: z87a022index.dgn PLOT DATE: 6/4/2009
 PROJECT LEADER: CRB DRAWN BY: SRB
 DESIGNED BY: PTS/DAM CHECKED BY: PTS
 CLD REF. NO.: 08-0159 SHEET 5 OF 160