STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3

MILE MARKER, STATION OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.42	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM DIA (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM DIA (in) 4.0Mod lb/ft 1.7	TUBULAR STEEL DIA (in) FND-ATION	TUBULAR STEEL DIA (in) 3.0 lb/ft 7.6	TUBULAR STEEL DIA (in) 3.5 lb/ft 9.0	TUBULAR STEEL DIA (in) 4.0 lb/ft 10.8	TUBULAR STEEL DIA (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
142.711 NB	ENTERING TOWN OF WHEELOCK	1	36	24	6.00						2					X		2															I-2		E-131
142.819 NB	EXIT 35 M.P.H.	1	48	60	20.00						2												2	X								W13-2		E-150
142.901 NB		1	18	18	2.25						1				X			1														OM1-1		E-150
142.904 NB	PARKING AREA	1	78	78		42.25					2												2	X									153	
142.944 NB		1	48	48	16.00						2												2	X								W4-1R		E-150
142.984 NB MED	ONE WAY	1	36	12	3.00						2					X		2														R6-1R		E-142
143.000 NB ~~143.800 NB~~	MILE 143.0 MILE 143.8 VA 4	5 ~~1~~	12	60 ~~48~~	25.00 ~~4.00~~						5 ~~1~~					X		5 ~~1~~														D10-3		E-139
143.000 NB	BRIDGE 97-3 I-91	1	6	10	0.42						1				X			1														VD-701	154	
143.340 NB MED		1	36	36	9.00						2					X		2														R3-4		E-143
143.400 NB	MOOSE	1	48	48	16.00																											VW-001	152	
	NEXT 10 MILES	1	30	24	5.00						2												2	X									152	
143.400 NB MED	MOOSE	1	48	48	16.00																											VW-001	152	
	NEXT 10 MILES	1	30	24	5.00						2												2	X									152	
143.730 NB	BRIDGE 98-8 I-91	1	6	10	0.42						1				X			1														VD-701	154	
144.000 NB ~~144.800 NB~~	MILE 144.0 MILE 144.8 VA 4	5 ~~1~~	12	60 ~~48~~	25.00 ~~4.00~~						5 ~~1~~					X		5 ~~1~~														D10-3		E-139
144.224 NB	BRIDGE 98-2 I-91	1	6	10	0.42						1				X			1														VD-701	154	
144.272 NB	ENTERING TOWN OF SHEFFIELD	1	36	24	6.00						2					X		2														I-2		E-131
												FT	FT	FT	FT 34.1	FT 148.0	FT	EA.	LB	LB	LB		LB 1064.0	LB	LB	LB							
SUBTOTALS SHEET 3					SF ~~155.5~~ ~~113.51~~	SF 42.25	EA.	SF				FT			FT 182.1				LB			EA. 10	LB 1064.0				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: LYNDON-DERBY
PROJECT NUMBER: IM IR 091-3(6)

FILE NAME:	080159_tss_mainline.xls	PLOT DATE:	5/7/2009
PROJECT LEADER:	CRB	DRAWN BY:	BDB
DESIGNED BY:	PTS	CHECKED BY:	DAM
TRAFFIC SIGN SUMMARY SHEET # 3		SHEET 62	OF 160