STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 5

MILE MARKER, STATION OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 / 2.42	2.5 / 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (in) 3.0 lb/ft 1.3	4.0 / 1.7	4.0Mod / 1.7	FND-ATION	TUBULAR STEEL DIA (in) 3.0 lb/ft 7.6	3.5 / 9.0	4.0 / 10.8	5.0 / 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
148.554 NB	BRIDGE 101-N I-91	1	6	10	0.42						1				X			1															VD-701	154	
149.000 NB → 149.800 NB	MILE 149.0 / MILE 149.8	5 ~~1~~	12	60 ~~48~~	25.00 ~~4.00~~						5 ~~1~~					X		5 ~~1~~															D10-3		E-139
150.000 NB → 150.800 NB	MILE 150.0 / MILE 150.8	5 ~~1~~	12	60 ~~48~~	25.00 ~~4.00~~						5 ~~1~~					X		5 ~~1~~															D10-3		E-139
150.237 NB	HIGHEST ELEVATION I-91 1856 FEET	1	54	48	18.00						2												2	X										144	
150.710 NB MED		1	36	36	9.00						2					X		2															R3-4		E-143
150.790 NB MED		1	36	36	9.00						2					X		2															R3-4		E-143
151.000 NB → 151.800 NB	MILE 151.0 / MILE 151.8	5 ~~1~~	12	60 ~~48~~	25.00 ~~4.00~~						5 ~~1~~					X		5 ~~1~~															D10-3		E-139
151.740 NB	BRIDGE 101-2N I-91	1	6	10	0.42						1				X			1															VD-701	154	
152.000 NB → 152.800 NB	MILE 152.0 / MILE 152.8	5 ~~1~~	12	60 ~~48~~	25.00 ~~4.00~~						5 ~~1~~					X		5 ~~1~~															D10-3		E-139
152.050 NB	BRIDGE 101-3N I-91	1	6	10	0.42						1				X			1															VD-701	154	
152.450 NB MED		1	36	36	9.00						2					X		2															R3-4		E-143
152.817 NB	ENTERING TOWN OF GLOVER ORLEANS CO.	1	36	30	7.50						2					X		2															I-2		E-131
153.000 NB → 153.800 NB	MILE 153.0 / MILE 153.8	5 ~~1~~	12	60 ~~48~~	25.00 ~~4.00~~						5 ~~1~~					X		5 ~~1~~															D10-3		E-139
153.000 NB	PARKING AREA 1 MILE	1	138	60		57.50					2												2			X								144	
153.390 NB MED		1	36	36	9.00						2					X		2															R3-4		E-143
153.430 NB	PARKING AREA NEXT RIGHT	1	138	60		57.50					2												2			X								144	
153.849 NB	EXIT 30 M.P.H.	1	48	60	20.00						2												2	X									W13-2		E-150
												FT	FT	FT	FT 24.6	FT 221.6	FT		EA.	LB	LB	LB		LB 419.6	LB	LB 630.8	LB								
SUBTOTALS SHEET 5					SF 207.76 ~~102.76~~	SF 115.00	EA.	SF				FT			FT 246.2					LB			EA. 8	LB 1050.4				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: LYNDON-DERBY
PROJECT NUMBER: IM IR 091-3(6)

FILE NAME:	080159_tss_mainline.xls	PLOT DATE:	5/7/2009
PROJECT LEADER:	CRB	DRAWN BY:	BDB
DESIGNED BY:	PTS	CHECKED BY:	DAM
TRAFFIC SIGN SUMMARY SHEET # 5		SHEET 64 OF 160	