STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 11

MILE MARKER, STATION OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (in) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0Mod lb/ft 1.7	TUBULAR STEEL DIA (in) FND-ATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
163.200 NB	MOOSE	1	48	48	16.00																												VW-001	152	
	NEXT 10 MILES	1	30	24	5.00						2												2	X									152	
163.200 NB MED	MOOSE	1	48	48	16.00																												VW-001	152	
	NEXT 10 MILES	1	30	24	5.00						2												2	X									152	
163.250 NB MED		1	36	36	9.00						2					X		2															R3-4		E-143
163.300 NB MED		1	36	36	9.00						2					X		2															R3-4		E-143
163.470 NB	BRIDGE 107-1 I-91	1	6	10	0.42						1				X			1															VD-701	154	
163.540 NB	ENTERING TOWN OF BROWNINGTON	1	36	24	6.00						2					X		2															I-2		E-131
164.000 NB 164.800 NB	MILE 164.0 → MILE 164.8	5 ~~1~~	12	60 ~~48~~	25.00 ~~4.00~~						5 ~~1~~					X		5 ~~1~~															D10-3		E-139
164.260 NB	BRIDGE 107-3 I-91	1	6	10	0.42						1				X			1															VD-701	154	
164.309 NB	ENTERING TOWN OF COVENTRY	1	36	24	6.00						2					X		2															I-2		E-131
165.000 NB 165.800 NB	MILE 165.0 → MILE 165.8	5 ~~1~~	12	60 ~~48~~	25.00 ~~4.00~~						5 ~~1~~					X		5 ~~1~~															D10-3		E-139
165.480 NB	WEIGH STATION PARKING AREA 1 MILE	1	156	84		91.00					2												2				X						148		
165.660 NB	ALL TRUCKS COMMERCIAL VEHICLES NEXT RIGHT	1	120	84		70.00					2												2				X						148		
165.820 NB	BRIDGE 108-N I-91	1	6	10	0.42						1				X			1															VD-701	154	
166.000 NB 166.800 NB	MILE 166.0 → MILE 166.8	5 ~~1~~	12	60 ~~48~~	25.00 ~~4.00~~						5 ~~1~~					X		5 ~~1~~															D10-3		E-139
166.130 NB	BRIDGE 108-1N I-91	1	6	10	0.42						1				X			1															VD-701	154	
												FT	FT	FT	FT 32.8	FT 160.6	FT		EA.	LB	LB	LB		LB 440.8	LB	LB	LB 899.5								
SUBTOTALS SHEET 11					~~148.68~~ 85.68 SF	161.00 SF	EA.	SF				FT			FT 193.4					LB			EA. 8	LB 1340.3				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: LYNDON-DERBY
PROJECT NUMBER: IM IR 091-3(6)

FILE NAME:	080159_tss_mainline.xls	PLOT DATE:	5/7/2009
PROJECT LEADER:	CRB	DRAWN BY:	BDB
DESIGNED BY:	PTS	CHECKED BY:	DAM
TRAFFIC SIGN SUMMARY SHEET # 11		SHEET 70	OF 160