STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 25

MILE MARKER, STATION OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (in) lb/ft 3.0 1.3	4.0 1.7	4.0Mod 1.7	TUBULAR STEEL DIA (in) lb/ft FND-ATION	3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
160.660 SB	Barton 6 St. Johnsbury 31	1	132	36		33.00					2												2	X										146	
160.826 SB	SPEED LIMIT 65	1	48	60	20.00																												R2-1		E-142
	MINIMUM 40	1	48	48	16.00						2												2		X								VR-141		E-142
160.926 SB		1	48	48	16.00																												VW-397	152	
	GROOVED SHOULDER	1	24	18	3.00						2												2	X									VP-396	152	
161.000 SB 161.800 SB	MILE 161.0 → MILE 161.8	5 ~~1~~	12	60 ~~48~~	25.00 ~~4.00~~						5 ~~1~~					X		5 ~~1~~															D10-3		E-139
161.026 SB	SOUTH	1	30	15	3.13																												M3-3		E-135
	91	1	36	36	9.00																												M1-1		E-135
	DIRECTIONS OF INTERSTATE SYSTEM	1	36	36	9.00						1												1	X									M1-10		E-135
161.080 SB MED		1	36	36	9.00						2					X		2															R3-4		E-143
161.107 SB	EMERGENCY STOPPING ONLY	1	48	36	12.00						2												2	X									R8-7		E-142
161.480 SB	BRIDGE 106-S I-91	1	6	10	0.42						1				X			1															VD-701	154	
161.547 SB MED	ONE WAY	1	36	12	3.00						2					X		2															R6-1R		E-142
161.607 SB		1	48	48	16.00						2												2	X									W4-1R		E-150
161.676 SB	EXIT 26	1	72	60		30.00					2												2	X										153	
161.684 SB		1	18	18	2.25						1				X			1															OM1-1		E-150
161.740 SB	BRIDGE 106-I I-91	1	6	10	0.42						1				X			1															VD-701	154	
												FT	FT	FT	FT 26.1	FT 72.9	FT		EA.	LB	LB	LB		LB 1064.8	LB 315.0	LB	LB							
											SUBTOTALS SHEET 25				SF ~~123.22~~ 143.80	SF 63.00	EA.	SF		FT				FT 99.0			LB		EA. 13	LB 1379.8		EA.	EA.	LB		

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: LYNDON-DERBY
PROJECT NUMBER: IM IR 091-3(6)

FILE NAME:	080159_tss_mainline.xls	PLOT DATE:	5/7/2009
PROJECT LEADER:	CRB	DRAWN BY:	BDB
DESIGNED BY:	PTS	CHECKED BY:	DAM
TRAFFIC SIGN SUMMARY SHEET # 25		SHEET 84	OF 160