STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 41

MILE MARKER, STATION OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (in) lb/ft 3.0 1.3	4.0 1.7	4.0Mod 1.7	TUBULAR STEEL DIA (in) FND-ATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
2.075 VT 122 LT	STOP	1	30	30	6.25						1					X		1															R1-1		E-143
2.092 VT 122 RT	WHEELOCK 4	1	72	12	6.00																												D2-1		E-123
	SHEFFIELD 6	1	72	12	6.00						2					X		2															D2-1		E-123
2.100 VT 122 LT	BARTON 17	1	72	12	6.00																												D1-1a		E-123
	NEWPORT 33	1	72	12	6.00																												D1-1a		E-123
	ST. JOHNSBURY 11	1	72	12	6.00						2												2	X									D1-1a		E-123
2.150 VT 122 LT	JCT	1	21	15	2.19																												M2-1		E-135
	INTERSTATE 91	1	24	24	4.00						1					X		1															M1-1		E-135
INT #25 0.090 RAMP A RT		1	36	36	9.00						2					X		2															W3-1a		E-150
0.128 RAMP A RT	SOUTH	1	24	12	2.00																												M3-3		E-136B
	NORTH	1	24	12	2.00																												M3-1		E-136B
	TO	1	24	12	2.00																												M4-5		E-136A
	VERMONT 16	1	24	24	4.00																												M1-5		E-136B
	VERMONT 16	1	24	24	4.00																												M1-5		E-136B
	5	1	24	24	4.00																												M1-4		E-136A
		1	21	15	2.19																												M6-1		E-136B
		1	21	15	2.19																												M6-1		E-136B
		1	21	15	2.19						2												2	X							#3	M6-1		E-136A
0.166 RAMP A RT	GLOVER 2	1	72	12	6.00																												D1-1a		E-123
	HARDWICK 21	1	72	12	6.00																												D1-1a		E-123
	BARTON 1	1	72	12	6.00																												D1-1a		E-123
	CRYSTAL LAKE 2	1	72	12	6.00						2												2	X									D1-1a		E-123
0.204 RAMP A LT	WRONG WAY	1	36	24	6.00																												R5-1a		E-143
		1	24	24	4.00						2					X		2															R9-4a		E-143
												FT	FT	FT	FT	FT 116.4	FT		EA.	LB	LB	LB		LB 541.3	LB	LB	LB							
												FT			FT 116.4					LB			EA. 6	LB 541.3				EA.	EA.	LB				
	SUBTOTALS SHEET 41				SF 110.01	SF	EA.	SF																											

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: LYNDON-DERBY
PROJECT NUMBER: IM IR 091-3(6)

FILE NAME: 080159_tss_interchanges.x
PROJECT LEADER: CRB
DESIGNED BY: PTS
TRAFFIC SIGN SUMMARY SHEET # 41
PLOT DATE: 5/7/2009
DRAWN BY: BDB
CHECKED BY: DAM
SHEET 100 OF 160