QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

TRNG.	EROSION CONTROL		BRIDGE			ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ESTIMATE AND ROUNDING
						500	500	LF	12'' CSP .064	601.0005	116
						150	150	LF	15'' CSP .064	601.0010	138
						1050	1050	LF	18'' CSP .064	601.0015	300
						150	150	LF	24'' CSP .064	601.0025	96
						150	150	LF	30'' CSP .079	601.0036	102
						150	150	LF	36'' CSP .079	601.0046	118
						90	90	LF	42'' CSP .109	601.0052	50
						150	150	LF	48'' CSP .109	601.0057	102
						750	750	LF	18'' PCCSP (PI) .064	601.0615	EST.
						150	150	LF	24'' PCCSP (PI) .064	601.0625	EST.
						150	150	LF	30'' PCCSP (PI) .079	601.0636	EST.
						150	150	LF	36'' PCCSP (PI) .079	601.0646	EST.
						225	225	LF	48'' PCCSP (PI) .109	601.0657	EST.
						275	275	LF	18'' RCP CLASS III	601.0815	175
						150	150	LF	24'' RCP CLASS III	601.0825	134
						150	150	LF	30'' RCP CLASS III	601.0835	EST.
						150	150	LF	30'' RCP CLASS IV	601.0836	EST.
						150	150	LF	36'' RCP CLASS III	601.0845	126
						150	150	LF	42'' RCP CLASS III	601.0850	142
						150	150	LF	48'' RCP CLASS III	601.0855	EST.
						10	10	EA	12'' CSP ELBOW .064	601.5005	6
						20	20	EA	18'' CSP ELBOW .064	601.5015	14
						10	10	EA	15'' CSPES .064	601.6010	EST.
						10	10	EA	18'' CSPES .064	601.6015	6
						10	10	EA	24'' CSPES .064	601.6025	EST.
						5	5	EA	30'' CSPES .079	601.6036	EST.
						5	5	EA	36'' CSPES .079	601.6046	4
						5	5	EA	42'' CSPES .109	601.6052	EST.
						5	5	EA	48'' CSPES .109	601.6057	EST.
						1500	1500	LF	RELAYING PIPE CULVERTS	601.99	396
						70000	70000	LF	CLEANING CULVERT PIPE IN PLACE (0'' - 24'' DIA. INCLUSIVE) (MOD.)	601.995	EST.
						2000	2000	LF	CLEANING CULVERT PIPE IN PLACE (GREATER THAN 24'' DIA.)	601.996	EST.
						2	2	CY	CEMENT RUBBLE MASONRY	602.15	EST.
						5	5	EA	CONCRETE CATCH BASIN W/CI GRATE	604.10	EST.
						10	10	EA	CONCRETE MANHOLE W/CI COVER	604.11	EST.
						25	25	EA	PRC CURB DROP INLET W/ CAST IRON GRATE	604.30	16
						10	10	EA	CHANGE ELEV OF DI, CB, OR MH	604.40	EST.

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

SURVEYED BY N/A DATE N/A
DRAWN BY KML DATE 3/95
SQUAD LEADER BOMBARDIER

DESIGN FILE NO. sada/87a008/da008.dgn
IPARM FILE da008a02.i DATE PLOTTED 12-MAR-1999

PROJ. NAME Hartford Sharon Royalton

PROJ. NO. IM IR 089-1(8)

SHEET 4 OF 260 SHEETS