QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

TRNG.	EROSION CONTROL		BRIDGE			ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ESTIMATE AND ROUNDING
			1500				1500	LF	TEMPORARY 4'' YELLOW LINE	646.61	103
			54850			47150	102000	LF	TEMPORARY 6'' WHITE LINE	646.614	440
			41784			43216	85000	LF	TEMPORARY 6'' YELLOW LINE	646.615	92
						2600	2600	LF	TEMPORARY 8'' WHITE LINE	646.62	30
						400	400	LF	TEMPORARY 12'' WHITE LINE	646.64	EST.
			30				30	LF	TEMPORARY 24'' STOP BAR	646.66	-
			3461			3039	6500	EA	LINE STRIPING TARGET	646.73	EST.
			21660			75340	97000	SF	BLACK PVMT. MARKING MASKING TAPE	646.86	414
	52000						52000	SY	GEOTEXTILE UNDER STONE FILL	649.31	EST.
						1000	1000	SY	GEOTEXTILE FOR UNDERDRAIN LINING	649.41	460
	10000						10000	SY	GEOTEXTILE FOR SILT FENCE	649.51	200
	1320						1320	LB	SEED	651.15	EST.
	660						660	LB	SEED-WINTER RYE	651.17	EST.
	11000						11000	LB	FERTILIZER	651.18	EST.
	44						44	TON	AGRICULTURAL LIMESTONE	651.20	EST.
	88						88	TON	HAY MULCH	651.25	EST.
	2000						2000	EA	HAY BALES FOR EROSION CONTROL	651.26	EST.
						2000	2000	CY	TOPSOIL	651.35	611
						100	100	SY	GRUBBING MATERIAL	651.40	EST.
	6400						6400	SY	EROSION MATTING	654.10	225
						2500	2500	SF	TRAFFIC SIGNS, TYPE A	675.20	EST.
						1650	1650	SF	TRAFFIC SIGNS, TYPE B	675.21	13
						180	180	SF	TRAFFIC SIGNS, TYPE B (MOD.)	675.21	EST.
						7800	7800	LF	FLANGED CHANNEL SIGN POST	675.301	80
						4600	4600	LB	W-SHAPED STEEL SIGN POST	675.31	48
						300	300	LB	TUBULAR ALUMINUM SIGN POST	675.32	20
						7700	7700	LB	TUBULAR STEEL SIGN POST	675.33	49
						11	11	EA	FOUNDATION FOR W-SHAPE STEEL POST 24'' DIAMETER	675.41	-
						4	4	EA	FOUNDATION FOR W-SHAPE STEEL POST 30'' DIAMETER	675.42	-
						72	72	EA	FOUNDATION FOR TUBULAR STEEL POST	675.43	-
						434	434	EA	REMOVING SIGNS	675.50	-
						11	11	EA	ERECTING SALVAGE SIGNS	675.60	-
						2250	2250	EA	DELINEATORS W/STEEL POSTS	676.10	-
						1300	1300	EA	REMOVAL OF EXISTING DELINEATORS	676.12	-
						1000	1000	EA	REMOVE & REPLACE REFLECTOR UNITS	676.15	EST.
			1				1	EA	TEMPORARY TRAFFIC SIGNAL SYSTEM	678.40	-
			1				1	EA	TEMPORARY DETECTOR	678.42	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

SURVEYED BY N/A DATE N/A
DRAWN BY NUTTER DATE 3/95
SQUAD LEADER BOMBARDIER
DESIGN FILE NO. sada/87a008/da008.dgn
IPARM FILE da008a05.I DATE PLOTTED 20-NOV-2000
PROJ. NAME Hartford Sharon Royalton
PROJ. NO. IM IR 089-1(8)
SHEET 7 OF 260 SHEETS