

EARTHWORK AND DRAINAGE SUMMARY SHEET FOR HARTFORD-SHARON-ROYALTON IR 089-1(8)

MILE MARKER	MILE MARKER	POS.	SOLID ROCK EXCAV. CY	COMM. EXCAV. CY	TRENCH EARTH CY	EXCAV. ROCK CY	EARTH BR. EXCAV. MATERIAL CY	TOPSOIL CY	CSP ELBOWS EA	CORRUGATED STEEL PIPE			REINFORCED CONCRETE PIPE			METAL END SECT. EA	ITEM NO. 616.47 TON	GEO. FOR STONE FILL SY	CRAN. BRK. FILL STRUCT. CY	CONC. CL B CY	REIN. STEEL LBS	REHAB DI EA	GRATE TYPE EA	ITEM # 619.17 EA	PRCCDI EA	STONE FILL		GEO. FOR UNDER-DRAIN SY	EROSION MATTING SY	CLEAN DITCH LF	REMARKS
										D	L	TH	D	L	CL											TYPE	CY				
NORTHBOUND:																															
17.69		OUT																			1									REHAB CURB DI	
17.77		OUT																			1									REHAB CURB DI	
17.81		OUT																			1									REHAB CURB DI	
17.86		MED																			1									REHAB DI & GRADE DITCH TO DRAIN	
17.86		OUT																			1									REHAB CURB DI	
17.90		OUT																			1		1						10	REHAB DI & OUTLET CLEAN DITCH	
17.93		CL																			2								40	OUTSIDE REHAB CURB DI, MEDIAN REHAB DI & CLEAN DITCH	
17.97		OUT																			1									REHAB CURB DI	
18.35		CL																			2									REHAB DI'S	
18.39		CL																			2		1						40	OUTSIDE REHAB CURB DI, MEDIAN REHAB DI & CLEAN DITCH	
18.40		CL			32		11			30	32	.079											1		II	3				OUTLET REPLACE 32' OF PIPE & NEW STONE PAD	
18.41		CL																			2		1							REHAB MED & CURB DI	
18.85		CL																			1		1							MEDIAN REHAB DI	
18.98		MED																			1		1							MEDIAN REHAB DI	
19.30		MED					10																							REPAIR SINK HOLE	
19.43		OUT																			1									REHAB CURB DI	
19.48		OUT																			1									REHAB CURB DI	
19.53		OUT																			1								10	REHAB CURB DI & OUTLET CLEAN DITCH	
19.55		OUT																			1									REHAB CURB DI	
19.81		OUT																			1									REHAB CURB DI	
19.82		MED					10																							REPAIR SINK HOLE	
19.85		OUT					20														1									REHAB CURB DI & REPAIR SINK HOLE	
19.88		MED					2			24											1		1						40	REHAB DI & CLEAN DITCH	
19.90		OUT																			1									REHAB CURB DI	
19.95		CL			11		2			18											2		1		1				40	MED. REHAB DI & CLEAN DITCH, OUTSIDE REHAB CURB DI & COVER, NEW PRCCDI OUTLET TO EXIST. DI	
20.00		OUT								12	4	.064									1		1						10	REHAB CURB DI & OUTLET CLEAN DITCH	
20.10		CL					2			18											2		2						60	MEDIAN REHAB DI & CLEAN DITCH, OUTSIDE REHAB CURB DI & OUTLET CLEAN DITCH	
20.49		OUT								12											1									REHAB CURB DI	
20.53		OUT								12											1									REHAB CURB DI	
20.63		OUT			35		47			18	30	.064	18	24	III					2.1	193		1-A	3	I	1			20	OUTLET REPLACE & BOLT LAST 3 SECTIONS OF PIPE, NEW STONE PAD, CLEAN DITCH, NEW DI & PIPE TIE TO EX. DI, REPAIR DITCH & SLOPE	
20.83		OUT								18													1						50	OUTLET CLEAN DITCH	
20.90		OUT								18													1							OUTLET PAVE EX. BIT. CONC. GUTTER	
21.08		OUT								18											1		1-B							REPLACE THROATED DI TOP W/ GRATE TOP	
21.18		CL					5			18											2		1						20	MEDIAN REHAB DI & CLEAN DITCH, OUTSIDE REHAB CURB DI	
21.41	21.58	OUT								12											1									ROYALTON REST AREA SEE SHEET #55	
21.23		OUT					30			12											1									REHAB CURB DI	
21.27		OUT								18											1		1						20	REHAB CURB DI & OUTLET CLEAN DITCH	
21.69		OUT								24													1						20	OUTLET CLEAN DITCH	
21.87	U-TURN	MED					25	5		18	48	.064																		REGRADE U-TURN SLOPES, EXTEND PIPE 36' ON NORTH END & 12' ON SOUTH END	
21.87		OUT								18											1									REHAB CURB DI	
21.93		OUT								18																					
21.95		CL								18																					

SEE REVISED DRAINAGE SHEETS 31A - 069A

DRAWN BY	Squad A	DATE	7/94
SQUAD LEADER	BOMBARDIER		
DESIGN FILE NO.	/sqda/87a008/da008dr.dgn		
IPARM FILE	da008d07.1	DATE PLOTTED	12-MAR-1999
PROJ. NAME	HARTFORD-SHARON-ROYALTON		
PROJ. NO.	IM IR 089-1(8)		
SHEET	38	OF	260 SHEETS

EARTHWORK AND DRAINAGE SUMMARY SHEET