

EARTHWORK AND DRAINAGE SUMMARY SHEET FOR HARTFORD-SHARON-ROYALTON IR 089-1(8)

MILE MARKER	MILE MARKER	POS.	SOLID ROCK EXCAV. CY	COMM. EXCAV. CY	TRENCH EARTH CY	EXCAV. ROCK CY	EARTH BR./EXCAV. MATERIAL CY	TOPSOIL CY	CSP ELBOWS EA	CORRUGATED STEEL PIPE			REINFORCED CONCRETE PIPE			METAL END SECT. EA	ITEM. NO. 16.47 TON	GEO. FOR STONE FILL SY	GRAN. BK/FILL STRUCT. CY	CONC. CL B CY	REIN. STEEL LBS	REHAB. DI EA	GRATE TYPE EA	ITEM # 619.17 EA	PRCCDI EA	STONE FILL		GEO. FOR UNDER-DRAIN SY	EROSION MATTING SY	CLEAN DITCH LF	REMARKS	
										D	L	TH	D	L	CL											TYPE	CY					
SOUTHBOUND:																																
7.71		OUT			11		3			15	12	.064									1		1			I	1			10	REHAB CURB DI, RELAY LAST 2 SECTIONS OF PIPE & NEW STONE PAD @ OUTLET	
7.72		OUT			15	1	4			24	8	.064											1		I	1			40	INLET CLEAN DITCH, OUTLET REMOVE CRADLE HW, RESET 3 LENGTHS OF PIPE		
7.81		OUT			20		2			12	30	.064									1		1						10	REHAB DI, REPLACE 30' OF PIPE & CLEAN DITCH		
7.87		OUT			16		6			12	24	.064									1		2			I	1				INLET REHAB DI, OUTLET REPLACE 24' OF PIPE & NEW STONE PAD	
7.92		OUT								12											1										REHAB CURB DI	
7.96		OUT								18													1							20	OUTLET CLEAN DITCH	
7.97		OUT								12											1										REHAB CURB DI	
8.11		CL			20	1	5			42													1		II	5			30	REMOVE CRADLE HW, OUTLET RELAY 12' PIPE & NEW STONE PAD		
8.15		OUT			9	1	3			12	12	.064									1		1			I	1			10	REHAB CURB DI, OUTLET REMOVE HW, REPLACE 12' OF PIPE & NEW STONE PAD	
8.21		OUT			10																				II	25					OUTLET NEW STONE LINED DITCH	
8.22		CL								18													1		II	5			20	OUTLET CLEAN & STONE LINE DITCH		
8.54		OUT								12											1										REHAB CURB DI	
8.57		OUT					20			12											1										REHAB CURB DI & OUTLET REPAIR SLOPE	
8.65		CL			35		2		URD	6	30										1		1				50		60	REHAB DI & CLEAN DITCH, OUTLET CLEAN DITCH, REPLACE 30' UDR & RELAY LAST 30' OF 24" PIPE		
8.75		MED					2			24											1		1							60	REHAB DI, CLEAN & REGRADE DITCH, OUTLET CLEAN DITCH	
8.84		OUT			15		25	10		30						48							1		II	15					SHARON SOUTHBOUND REST AREA- OUTLET USE 8' X 25' STONE PAD W/GEOTEXTILE UNDER STONE FILL, FILL EROSION AREA	
8.93		CL			19		6			18											2		2			I	2		100	MED REHAB DI & CLEAN DITCH, OUTLET REHAB DI, RELAY & BOLT LAST 3 SECTIONS & NEW STONE PAD		
9.00		CL			20		7																2		I	1			20	INLET RESET PIPE, OUTLET CLEAN DITCH, RELAY & BOLT LAST 3 SECTIONS & NEW STONE PAD		
9.47		CL								18													1						20	OUTLET CLEAN DITCH		
9.49		OUT								12											1										REHAB CURB DI	
9.54		OUT								12											1										REHAB CURB DI	
9.62		CL								18													1						20	OUTLET CLEAN DITCH		
9.70		CL					2																2						60	CLEAN DITCHES		
9.82		CL								66													1						40	OUTLET CLEAN DITCH		
9.93		CL			9	2	3			24	8	.064											2		I	1			20	INLET REPLACE FULL HW & 8' OF PIPE, OUTLET NEW STONE PAD & CLEAN DITCH		
10.00		OUT			1					24																I	1		20	OUTLET CLEAN DITCH & NEW STONE PAD		
10.17		CL			3	2	5	1		24													1						20	INLET REMOVE HW & REPLACE W/ NEW DI, OUTLET CLEAN & REGRADE DITCH REPAIR SLOPE		
10.21		OUT					20																									
10.26		CL			29					30													2		II	3			20	EXCAVATE PIPE ENDS, FLUSH PIPE & OUTLET CLEAN DITCH & NEW STONE PAD		
10.38		CL			5	1				18													2		I	1			20	INLET REPLACE FULL HW, OUTLET CLEAN DITCH, FILL WASH OUT AREA W/ STONE FILL & NEW STONE PAD		
10.58		CL			14		3			36	8	.079				1							1		II	22					INLET REPLACE 8' OF PIPE, NEW MES & OUTLET NEW STONE PAD	
10.66		OUT								12											1		1						10	REHAB CURB DI, OUTLET CLEAN DITCH		
10.73		OUT								18											1										REHAB CURB DI	
10.78		OUT								18											1										REHAB CURB DI	
10.84		CL					2			18													2						60	REHAB MED. & OUT DI'S & CLEAN DITCHES		
10.89		CL					2			18													2						60	REHAB MED. & OUT DI'S & CLEAN DITCHES		
SHEET 41	TOTALS:				251	8	122	11		12	66	.064				48			7.2	181.3	21	1-A	30		I	10			750			
										15	12	.064														II	79					
										24	16	.064																				
										36	8	.079				1																
									UDR	6	30																	50				EARTHWORK AND DRAINAGE SUMMARY SHEET

DRAWN BY	Squad A	DATE	7/94
SQUAD LEADER	BOMBARDIER		
DESIGN FILE NO.	/sqda/87a008/da008dr.dgn		
IFARM FILE	da008d10.1	DATE PLOTTED	J2-MAR-1999
PROJ. NAME	HARTFORD-SHARON-ROYALTON		
PROJ. NO.	IM IR 089-1(8)		
SHEET	41	OF	260 SHEETS