

EARTHWORK AND DRAINAGE SUMMARY SHEET FOR HARTFORD-SHARON-ROYALTON IR 089-1(8)

MILE MARKER	MILE MARKER	POS.	SOLID ROCK EXCAV. CY	COMM. EXCAV. CY	TRENCH EARTH CY	EXCAV. ROCK CY	EARTH BR. / EXCAV. MATERIAL CY	TOPSOIL CY	CSP ELBOWS EA	CORRUGATED STEEL PIPE			REINFORCED CONCRETE PIPE			METAL END SECT. EA	ITEM NO. 616, 47 TON	GEO. FOR STONE FILL SY	GRAN. SK. FILL STRUCT. CY	CONC. CL B CY	REIN. STEEL LBS	REHAB DI EA	GRATE TYPE EA	ITEM # 619, 7 EA	PRCCDI EA	STONE FILL		GEO. FOR UNDER-DRAIN SY	EROSION MATTING SY	CLEAN DITCH LF	REMARKS
										D	L	TH	D	L	CL											TYPE	CY				
SOUTHBOUND:																															
RAMP C																															
6+25	12+00	LT																												575	CLEAN DITCH LINE
7+00	11+35	RT																			1								435	REHAB DI & CLEAN DITCH LINE	
13.35		OUT								12											1										REHAB CURB DI
13.46		OUT								12											1										REHAB CURB DI
13.49		CL								18													1						40	OUTLET CLEAN PIPE END & DITCH	
13.74	U-TURN	MED			9		26	5		18	8	.064							2.8	239	1	1-A	2			1	1				REGRADE U-TURN SLOPES, NEW DI TIE TO EXIST. DI, RAISE & CAP EXIST. DI & OUTLET FILL 3' X 3' X 3' SINK HOLE
13.85		OUT			1					12											1					1	1		10	REHAB CURB DI, OUTLET CLEAN DITCH & NEW STONE PAD	
14.29		OUT								18													1						20	OUTLET CLEAN DITCH	
14.56		OUT								12											1										REHAB CURB DI
14.85		OUT								12											1		1								REHAB DI
15.04		OUT								12											1										REHAB CURB DI TO MEET NEW CURB LINE
15.09		OUT								12											1										REHAB DI
15.19		OUT								12																			20	CLEAN AROUND DI	
15.71										12											1								10	REHAB DI & GRADE DITCH	
16.03		OUT								36													1			11	15		30	OUTLET CLEAN DITCH & NEW STONE PAD	
16.21		OUT								24													1						20	INLET CLEAN DITCH	
16.35		OUT								18													1						20	INLET CLEAN DITCH	
16.42		CL								18											2		2						80	REHAB OUTSIDE & MED DI'S & CLEAN DITCHES	
16.54		MED								24											1		1						40	REHAB MED DI & CLEAN DITCH	
16.61		OUT								18											1		1								REHAB DI
16.63		MED								18											1		1						40	REHAB MED DI & CLEAN DITCH	
16.96		OUT								12											1										REHAB CURB DI TO MATCH NEW CURB LINE
17.00		OUT		50						12											1				1	50					REHAB CURB DI TO MATCH NEW CURB LINE & FIX 5 SINK HOLES IN MED
17.03		OUT			11					12	4	.064									1				1						REHAB & CAP EXIST. DI, NEW PRCCDI TO BE TIED TO EXIST. DI
17.07		OUT								12											1		1						10	REHAB CURB DI & OUTLET CLEAN DITCH	
17.12		OUT			20		40			12											1										REHAB DI TO MATCH CURB, RELAY LAST 3 SECT. OF PIPE & REGRADE SLOPE
17.16		OUT			16		6			12											1				1	2					REHAB CURB DI TO MATCH NEW CURB LINE, RELAY LAST 3 SECTION OF PIPE & STONE PAD @ OUTLET
17.20		OUT			6			2		12	8	.064									1		1		11	75		10			REHAB CURB DI, OUTLET CLEAN DITCH & REPLACE LAST SECTION OF PIPE & STONE LINE DITCH
17.36		OUT								18											1		1								REHAB DI
17.77		OUT								18											1										REHAB CURB DI
17.81		CL								18											2		1								REHAB CURB & MED DI'S
17.86		OUT								18											1		1						20	REHAB CURB DI & OUTLET CLEAN DITCH	
17.90		OUT								12											1		1						10	REHAB CURB DI & OUTLET CLEAN DITCH	
18.25		OUT					2			18											1		1						40	REHAB DI & CLEAN DITCH	
18.39		OUT								18											1		1						20	REHAB DI, OUTLET CLEAN DITCH	
18.43		OUT								18																			20	CLEAN PAVED GUTTER	
18.48		OUT					2			18											1		1						40	REHAB DI & CLEAN DITCH	
18.80	18.85	OUT		10																					1	5			200	STONE FILL @ INLET & REGRADE DITCH TO DRAIN	
19.03		OUT																			1		1								REHAB DI
19.09		OUT					2			24											1		1						40	REHAB DI & CLEAN DITCH	

SHEET 43 TOTALS: **SEE REVISED DRAINAGE SHEETS 31A - 069A**

DRAWN BY	Squad A	DATE	7/94
SQUAD LEADER	BOMBARDIER		
DESIGN FILE NO.	/sqda/87a008/da008dr.dgn		
IPAFM FILE	da008di2.1	DATE PLOTTED	12-MAR-1999
PROJ. NAME	HARTFORD-SHARON-ROYALTON		
PROJ. NO.	IM IR 089-1(8)		
SHEET	43	OF	260 SHEETS