STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.16	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUNDATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	REFLECTORIZED SIGNS	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																								
0.09 SB	BRIDGE 2 I-89	1	6"	8"	.33						1	X																						VD-701		E-134
0.16 SB	BRIDGE 2-1 I-89	1	6"	8"	.33						1	X																						VD-701		E-134
0.39 SB	BRIDGE 2-2 I-89	1	6"	8"	.33						1	X																						VD-701		E-134
0.54 SB	BRIDGE 3 I-89	1	6"	8"	.33						1	X																						VD-701		E-134
0.64 SB	BRIDGE 4 I-89	1	6"	8"	.33						1	X																						VD-701		E-134
0.69 SB	BRIDGE 5 I-89	1	6"	8"	.33						1	X																						VD-701		E-134
0.87 SB LT.		1	36"	36"	9						1			X																				R3-4		E-143
0.89 SB	BRIDGE 5-1 I-89	1	6"	8"	.33						1	X																						VD-701		E-134
1.15 SB	BRIDGE 6-S I-89	1	6"	8"	.33						1	X																						VD-701		E-134
1.18 SB	BRIDGE 6-1 I-89	1	6"	8"	.33						1	X																						VD-701		E-134
1.47 SB	BRIDGE 6-2S I-89	1	6"	8"	.33						1	X																						VD-701		E-134
2.32 SB	BRIDGE 6-3 I-89	1	6"	8"	.33						1	X																						VD-701		E-134
2.59 SB	BRIDGE 6-4 I-89	1	6"	8"	.33						1	X																						VD-701		E-134
2.70 SB	BRIDGE 6-5 I-89	1	6"	8"	.33						1	X																						VD-701		E-134
3.05 SB	BRIDGE 6-6 I-89	1	6"	8"	.33						1	X																						VD-701		E-134
3.17 SB	SPEED LIMIT 65	1	48"	60"		20																												R2-1		E-142
												FT 196		FT 14	FT		FT		EA	LB		LB		LB		LB	LB								
TOTALS					SF 13.62	SF 20	EA.	SF				FT 210			FT					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: HARTFORD-SHARON-ROYALTON	PROJECT NO.: IM IR 089-1(8)
DESIGN FILE NAME: ta008sum.dgn IPARM FILE NAME: ta008s01.i SURVEYED BY: SQUAD LEADER: ABK	PLOT DATE: 09-NOV-2000 SURVEY DATE: DRAWN BY: JHK SHEET: 203 OF 260