STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.16	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	REQUIRED SIGNING	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																							
	MINIMUM 40	1	48"	48"	16						2												2	X									VR-141		E-142
3.27 SB	BRIDGE 7 I – 89	1	6"	8"	.33						1	X																					VD-701		E-134
3.30 SB	SOUTH	1	30"	15"	3.13																												M3-3		E-135
	INTERSTATE 89	1	36"	36"	9																												M1-1		E-135
	EISENHOWER INTERSTATE SYSTEM	1	36"	36"	9						1												1	X											E-135
3.33 SB	BRIDGE 7-1 I – 89	1	6"	8"	.33						1	X																					VD-701		E-134
3.42 SB	BRIDGE 7-2 I – 89	1	6"	8"	.33						1	X																					VD-701		E-134
3.57 SB LT.	ONE WAY	1	36"	12"	3						2			X																			R6-1R		E-142
3.62 SB		1	48"	48"	16						2			X																			W4-1		E-150
3.77 SB	BRIDGE 7-3 I – 89	1	6"	8"	.33						1	X																					VD-701		E-134
4.01 SB	BRIDGE 8 I – 89	1	6"	8"	.33						1	X																					VD-701		E-134
4.03 SB	EXIT 1	1	96"	24.5"		20																													E-131
	4 Woodstock Quechee	1	204"	120"		170					2																						SEE DETAIL	237	
		6	30"	30"	37.5						3																	3		X	W8X18		BOLT TENSION 18.44 KIPS		E-132
4.21 SB	BRIDGE 8-1 I – 89	1	6"	8"	.33						1	X																					VD-701		E-134
4.27 SB	BRIDGE 9 I – 89	1	6"	8"	.33						1	X																					VD-701		E-134
												FT 98		FT 56	FT	FT	FT		EA	LB	LB	LB		LB 320	LB	LB	LB								
												FT 154			FT					LB			EA. 3	LB 320				EA. 3		EA.	LB 768.6				
TOTALS					SF 95.94	SF 190	EA.	SF																											

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: HARTFORD-SHARON-ROYALTON	PROJECT NO.: IM IR 089-1(8)
DESIGN FILE NAME: ta008sum.dgn IPARM FILE NAME: ta008s02.i SURVEYED BY: SQUAD LEADER: ABK	PLOT DATE: 09-NOV-2000 SURVEY DATE: DRAWN BY: JHK SHEET: 204 OF 260