STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.16	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	FOUND-ATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	REFLECTORIZED SIGNS	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																							
8.73 SB LT.	ONE WAY	1	12"	36"	3						2			X																				R6-1R		E-142
9.48 SB	BRIDGE 12-3S I-89	1	6"	8"	.33						1	X																						VD-701		E-134
9.62 SB LT.		1	36"	36"	9						1			X																				R3-4		E-143
9.64 SB LT.		1	36"	36"	9						1			X																				R3-4		E-143
9.84 SB	BRIDGE 12-4S I-89	1	6"	8"	.33						1	X																						VD-701		E-134
9.89 SB	BRIDGE 13-S I-89	1	6"	8"	.33						1	X																						VD-701		E-134
10.86 SB	BRIDGE 13-1 I-89	1	6"	8"	.33						1	X																						VD-701		E-134
11.76 SB	BRIDGE 13-2 I-89	1	6"	8"	.33						1	X																						VD-701		E-134
12.34 SB	BRIDGE 14 I-89	1	6"	8"	.33						1	X																						VD-701		E-134
12.38 SB	BRIDGE 14-1 I-89	1	6"	8"	.33						1	X																						VD-701		E-134
12.90 SB	SPEED LIMIT 65	1	48"	60"		20																												R2-1		E-142
	MINIMUM 40	1	48"	48"	16						2												2	X										VR-141		E-142
13.00 SB	MILE 1 3	1	12"	36"	3						1			X																				D10-2		E-139
13.08 SB	SOUTH	1	30"	15"	3.13																													M3-3		E-135
	INTERSTATE 89	1	36"	36"	9																													M1-1		E-135
	EISENHOWER INTERSTATE SYSTEM	1	36"	36"	9						1												1	X												E-135
												FT 98		FT 70	FT	FT	FT		EA	LB	LB	LB		LB 155	LB	LB	LB								
TOTALS					SF 63.44	SF 20	EA.	SF				FT 168			FT					LB			EA. 3	LB 155				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: HARTFORD-SHARON-ROYALTON	PROJECT NO.: IM IR 089-1(8)
DESIGN FILE NAME: tq008sum.dgn IPARM FILE NAME: tq008s04.i SURVEYED BY: SQUAD LEADER: ABK	PLOT DATE: 09-NOV-2000 SURVEY DATE: DRAWN BY: JHK SHEET: 206 OF 200