STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.16	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	REQUIRED SIGNING	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																							
14.63 SB LT.		1	12"	36"	3						1			X																			OM-3		E-120
14.78 SB LT.		1	36"	36"	9						1			X																			R3-4		E-143
15.00 SB	MILE 1 5	1	12"	36"	3						1			X																			D10-2		E-139
15.05 SB	BRIDGE 19 I – 89	1	6"	8"	.33						1	X																					VD-701		E-134
15.10 SB	BRIDGE 20 I – 89	1	6"	8"	.33						1	X																					VD-701		E-134
15.58 SB	BRIDGE 20-1 I – 89	1	6"	8"	.33						1	X																					VD-701		E-134
15.82 SB	BRIDGE 20-2 I – 89	1	6"	8"	.33						1	X																					VD-701		E-134
16.00 SB	MILE 1 6	1	12"	36"	3						1			X																			D10-2		E-139
16.22 SB	BRIDGE 20-3 I – 89	1	6"	8"	.33						1	X																					VD-701		E-134
17.00 SB	BRIDGE 20-4 I – 89	1	6"	8"	.33						1	X																					VD-701		E-134
17.45 SB	BRIDGE 21 I – 89	1	6"	8"	.33						1	X																					VD-701		E-134
17.80 SB	BRIDGE 21-1 I – 89	1	6"	8"	.33						1	X																					VD-701		E-134
17.86 SB		1	36"	36"	9						1			X																			R3-4		E-143
18.13 SB	BRIDGE 21-2 I – 89	1	6"	8"	.33						1	X																					VD-701		E-134
18.16 SB	BRIDGE 22 I – 89	1	6"	8"	.33						1	X																					VD-701		E-134
19.50 SB LT.		1	48"	48"	16						2			X																			W1-2R		E-151
												FT 140		FT 98	FT	FT	FT		EA	LB	LB	LB		LB	LB	LB	LB								
TOTALS					SF 46.3	SF	EA.	SF				FT 238			FT					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: HARTFORD-SHARON-ROYALTON	PROJECT NO.: IM IR 089-1(8)
DESIGN FILE NAME: ta008sum.dgn IPARM FILE NAME: ta008s06.i SURVEYED BY: SQUAD LEADER: ABK	PLOT DATE: 09-NOV-2000 SURVEY DATE: DRAWN BY: JHK SHEET: 208 OF 260