STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGNS REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																							
19.85 SB	BRIDGE 22-1 I-89	1	6"	8"	.33						1	X																					VD-701		E-134
19.94 SB	BRIDGE 23 I-89	1	6"	8"	.33						1	X																					VD-701		E-134
20.00 SB	BRIDGE 23-1 I-89	1	6"	8"	.33						1	X																					VD-701		E-134
20.54 SB	BRIDGE 23-2 I-89	1	6"	8"	.33						1	X																					VD-701		E-134
21.21 SB	BRIDGE 23-3 I-89	1	6"	8"	.33						1	X																					VD-701		E-134
21.28 SB	BRIDGE 24 I-89	1	6"	8"	.33						1	X																					VD-701		E-134
21.33 SB	Sharon 8 / White River Jct. 24	1					X				2											2				X						NEW POSTS ONLY		
21.52 SB	SPEED LIMIT 65	1	48"	60"		20																											R2-1		E-142
	MINIMUM 40	1	48"	48"	16						2											2	X										VR-141		E-142
21.80 SB	SOUTH	1	30"	15"	3.125																												M3-1		E-135
	INTERSTATE 89	1	36"	36"	9																												M1-1		E-135
	EISENHOWER INTERSTATE SYSTEM	1	36"	36"	9						1											1	X												E-135
21.85 SB	BRIDGE 24-1 I-89	1	6"	8"	.33						1	X																					VD-701		E-134
21.88 SB	BRIDGE 25 I-89	1	6"	8"	.33						1	X																					VD-701		E-134
												FT 112	FT	FT	FT	FT	FT		EA	LB	LB	LB		LB 115	LB	LB	LB 350								
	TOTALS				SF 39.77	SF 20	EA. 1	SF				FT 112			FT					LB			EA. 5	LB 465				EA.	EA.	LB					
	SOUTHBOUND TOTALS				SF 341.35	SF 20	EA. 1	SF				FT 1288			FT					LB			EA. 11	LB 940				EA. 7	EA.	LB 2098.98					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: HARTFORD-SHARON-ROYALTON	PROJECT NO.: IM IR 089-1(8)
DESIGN FILE NAME: tq008sum.dgn IPARM FILE NAME: tq008s07.i SURVEYED BY: SQUAD LEADER: ABK	PLOT DATE: 09-NOV-2000 SURVEY DATE: DRAWN BY: JHK SHEET: 209 OF 260