STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.16	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	REFLECTORIZED SIGNS	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STD. SHEET NUMBER
												OPTION ITEMS																							
13.70 NB	BRIDGES FREEZE BEFORE ROAD	1	48"	48"	16						2			X																				VW-005		E-150
13.76 NB LT.		1	36"	36"	9						1			X																				R3-4		E-143
13.85 NB	NORTH	1	30"	15"	3.13																													M3-1		E-135
	INTERSTATE 89		36"	36"	9																													M1-1		E-135
	EISENHOWER INTERSTATE SYSTEM		36"	36"	9						1												1	X											E-135
13.91 NB	BRIDGE 16-N I – 89	1	6"	8"	.33						1	X																						VD-701		E-134
14.25 NB	SPEED LIMIT 65	1	48"	60"		20																												R2-1		E-142
	MINIMUM 40	1	48"	48"	16						2												2	X										VR-141		E-142
14.38 NB LT.		1	12"	36"	3						1			X																				OM-3		E-120
14.38 NB RT.		1	12"	36"	3						1			X																				OM-3		E-120
14.38 NB	BRIDGE 17-N I – 89	1	6"	8"	.33						1	X																						VD-701		E-134
14.63 NB	BRIDGE 18-N I – 89	1	6"	8"	.33						1	X																						VD-701		E-134
14.76 NB LT.		1	36"	36"	9						1			X																				R3-4		E-143
14.96 NB LT.		1	36"	36"	9						1			X																				R3-4		E-143
14.98 NB	BRIDGE 19 I – 89	1	6"	8"	.33						1	X																						VD-701		E-134
15.00 NB	MILE 1 5	1	12"	36"	3						1			X																				D10-2		E-139
												FT 56		FT 112	FT	FT	FT		EA	LB	LB	LB		LB 303.8	LB	LB	LB							
TOTALS					SF 90.45	SF 20	EA.	SF				FT 168			FT					LB			EA. 3	LB 303.8				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: HARTFORD-SHARON-ROYALTON	PROJECT NO.: IM IR 089-1(8)
DESIGN FILE NAME: †a008sum.dgn IPARM FILE NAME: †a008sl3.I SURVEYED BY: SQUAD LEADER: ABK	PLOT DATE: 09-NOV-2000 SURVEY DATE: DRAWN BY: JHK SHEET: 215 OF 260