STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (In) lb/ft 1.75 (1.88)	2.0 (2.16)	2.5 (3.35)	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) lb/ft 3.0 (1.3)	4.0 (1.7)	4.0 MOD (1.7)	TUBULAR STEEL Ø (In) FOUNDATION	3.0 (7.6)	3.5 (9.0)	4.0 (10.8)	5.0 (14.6)	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
20.54 NB	BRIDGE 23-2 I-89	1	6"	8"	.33						1	X																					VD-701		E-134
21.21 NB	BRIDGE 23-3 I-89	1	6"	8"	.33						1	X																					VD-701		E-134
21.28 NB	BRIDGE 24 I-89	1	6"	8"	.33						1	X																					VD-701		E-134
21.29 NB	VERMONT 107	1	48"	36"	12																												MI-5		E-136B
	VERMONT 14	1	36"	36"	9																												MI-5		E-136B
21.78 NB	BRIDGES FREEZE BEFORE ROAD	1	48"	48"	16						2			X																			VW-005		E-150
21.82 NB	VERMONT 107	1	48"	36"	12																												MI-5		E-136B
	VERMONT 14	1	36"	36"	9																												MI-5		E-136B
21.85 NB	BRIDGE 24-1 I-89	1	6"	8"	.33						1	X																					VD-701		E-134
21.88 NB	BRIDGE 25 I-89	1	6"	8"	.33						1	X																					VD-701		E-134
21.93 NB	BRIDGE 26-N I-89	1	6"	8"	.33						1	X																					VD-701		E-134
												FT 84	FT	FT 28	FT	FT	FT		EA	LB	LB	LB		LB	LB	LB	LB								
TOTALS		SF 59.98	SF	EA.	SF							FT 112			FT					LB			EA.	LB				EA.	EA.	LB					
N. B. TOTALS		409.51	926.5	1								1414											13	1549.8				4	4	2453					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S 'SIGN POST DESIGN GUIDELINE.'

PROJECT: HARTFORD-SHARON-ROYALTON	PROJECT NO.: IM IR 089-1(8)
DESIGN FILE NAME: ta008sum.dgn	PLOT DATE: 09-NOV-2000
IPARM FILE NAME: ta008sl5.1	SURVEY DATE:
SURVEYED BY:	DRAWN BY: JHK
SQUAD LEADER: ABK	SHEET: 217 OF 260