STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (In)	SIGN DIMENSIONS HEIGHT (In)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.0 lb/ft 2.16	SQUARE STEEL (In) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (In) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (In) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (In) FOUND-ATION	TUBULAR STEEL Ø (In) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (In) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (In) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (In) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	REQUIRED SIGNING	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																							
INT. #1 RAMP C RT	SOUTH		30"	15"	3.13																												M3-3		E-135
	INTERSTATE 89		36"	36"	9																												M1-1		E-135
	↑		21"	15"	2.19						1									X													M6-3		E-135
	TURN SIGNAL REQUIRED BEFORE CHANGING LANES		36"	36"	9																												VR-002		E-142
	PROHIBITED PEDESTRIANS HITCHHIKERS ANIMALS BICYCLES FARM MACHINERY SNOW VEHICLES		36"	36"	9						2												2	X									VR-046		E-142
INT. #1 RAMP C LT.			24"	24"	4						1									X													R3-2 MOUNT ACROSS FROM GORE		E-143
INT. #1 RAMP D LT			18"	18"	2.25						1	X																					OM-1		E-150
INT. #1 RAMP D LT	EXIT 1 ↗		72"	60"		30					2												2	X											E-131
INT. #1 RAMP D RT	WRONG WAY		36"	24"	6																												R5-1A		E-143
			24"	24"	4						1			X																			R9-4A MOUNT FACING OPPOSITE TRAFFIC		E-143
INT. #1 RAMP D LT	WRONG WAY		36"	24"	6						1			X																			R5-1A MOUNT FACING OPPOSITE TRAFFIC		E-143
INT. #1 QUECHEE ST. HWY (MED)	↰ STOP		24" 30"	30" 30"	5 6.25																												R4-7 R1-1		E-142 E-143
			18" 18"	18" 18"	2.25 2.25						1			X																			OM-1 OM-1 MOUNT BACK TO BACK		E-150 E-150
												FT 14	FT	FT 42	FT	FT	FT		EA	LB 33.8	LB	LB		LB 532	LB	LB	LB								
		TOTALS			SF 70.32	SF 30	EA.	SF				FT 56			FT					LB 33.8			EA. 4	LB 532				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S 'SIGN POST DESIGN GUIDELINE.'

INTERCHANGE #1 QUECHEE

PROJECT: HARTFORD-SHARON-ROYALTON	PROJECT NO.: IM IR 089-1(8)
DESIGN FILE NAME: tq008sum.dgn IPARM FILE NAME: tq008s20.i SURVEYED BY: SQUAD LEADER: ABK	PLOT DATE: 09-NOV-2000 SURVEY DATE: DRAWN BY: JHK SHEET: 222 OF 260