STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	REQUIRED SIGNS	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																							
INT. #1 QUECHEE ST. HWY LT	STOP / DO NOT ENTER		30" / 30"	30" / 30"	6.25 / 6.25																												R1-1 R5-1		E-143 / E-143
	ONE WAY / ONE WAY		36" / 36"	12" / 12"	3 / 3						1			X																			R6-1L R6-1R SEE STD E-160 FOR MOUNTING DETAIL		E-142 / E-142
INT. #1 QUECHEE ST. HWY (MED)	WRONG WAY		36"	24"	6						1			X																			R5-1A MOUNT FACING OPPOSITE TRAFFIC		E-143
INT. #1 QUECHEE ST. HWY LT	WRONG WAY / QUECHEE 6		36" / 72"	24" / 10"	6 / 5																												R5-1A D1-1 MOUNT BACK TO BACK		E-143 / E-123
	WOODSTOCK 10		72"	10"	5																												D1-1		E-123
	2 FOOD		54"	7.5"	2.81																														E-133
	PHONE		54"	7.5"	2.81																														E-133
	FUEL		54"	7.5"	2.81																														E-133
	2 LODGING 3		54"	7.5"	2.81																														E-133
	CAMPING		54"	7.5"	2.81																														E-133
	INFORMATION		54"	7.5"	2.81						2												2	X											E-133
INT. #1 QUECHEE ST. HWY LT	WEST / EAST		24" / 24"	12" / 12"	2 / 2																												M3-4 M3-2		E-136
	4 / 4		24" / 24"	24" / 24"	4 / 4																												M1-4 M1-4		E-136
			21" / 21"	15" / 15"	2.19 / 2.19						2			X																			M5-1 M5-1		E-136
INT. #1 QUECHEE ST. HWY. (MED)			24"	30"	5																												R4-7		E-142
			18" / 18"	18" / 18"	2.25 / 2.25						1			X																			OM-1 OM-1 MOUNT BACK TO BACK		E-150
												FT	FT	FT 70	FT	FT	FT		EA	LB	LB	LB		LB 258.4	LB	LB	LB							
TOTALS			SF 83.25	SF	EA.	SF						FT 70			FT					LB			EA. 2	LB 258.4				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

INTERCHANGE #1 QUECHEE

PROJECT: HARTFORD-SHARON-ROYALTON	PROJECT NO.: IM IR 089-1(8)
DESIGN FILE NAME: ta008sum.dgn IPARM FILE NAME: ta008s21.t SURVEYED BY: SQUAD LEADER: ABK	PLOT DATE: 09-NOV-2000 SURVEY DATE: DRAWN BY: JHK SHEET: 223 OF 260