STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75	2.0	2.5	ANCHOR	SERVICE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0	4.0	4.0 MOD	TUBULAR STEEL Ø (in) FOUND-ATION	lb/ft 3.0	3.5	4.0	5.0	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																							
INT #1 US 4 5.80 RT	4 / INTERSTATE 89 / INTERSTATE 91		24" 24" 24"	24" 24" 24"	4 4 4																											M1-4 M1-1 M1-1		E-136A E-135 E-135
	↑ ↑ ↱		21" 21" 21"	15" 15" 15"	2.19 2.19 2.19						2												2	~~X~~							X	M6-3 M6-3 M5-1		E-136 E-135 E-135
INT #1 US 4 5.81 LT	QUECHEE 6		72"	10"	5																											D1-1		E-123
	WOODSTOCK 10		72"	10"	5																											D1-1		E-123
	RUTLAND 41		72"	10"	5						2			X																		D1 1		E-123
INT #1 US 4 5.84 RT	↑ ↱ ONLY		30"	30"	6.25						1			X																		VR-921		E-145A
INT #1 US 4 5.85 RT	SOUTH / SOUTH		24" 24"	12" 12"	2 2																											M3-3 M3-3		E-135
	INTERSTATE 89 / INTERSTATE 89		24" 24"	24" 24"	4 4																											M1-1 M1-1		E-135
	← →		21" 21"	15" 15"	2.19 2.19						2			X									2	~~X~~								M6-1 M6-1 MOUNT BACK TO BACK		E-135
INT #1 US 4 5.85 LT	WEST		24"	12"	2																											M3-4		E-136
	4		24"	24"	4						1									X												M1-4		E-136
INT #1 US 4 5.88 LT	TO		24"	12"	2																											M1-5		E-135
	EAST / NORTH		24" 24"	12" 12"	2 2																											M3 2 M3 1		E-136 E 135
	4 / INTERSTATE 89		24" 24"	24" 24"	4 4						2			X									2	~~X~~								M1-4 M1-1		E-136 E-135
INT #1 US 4 5.94 LT	↑ WOODSTOCK 10		72"	10"	5																											D1-1		E 123
	↑ RUTLAND 42		72"	10"	5																											D1-1		E-123
												FT	FT	FT 42	FT	FT	FT		EA	LB 24.7	LB	LB		LB 273.6	LB	LB	LB							
		TOTALS			SF 86.20	SF	EA.	SF				FT 42			FT					LB 24.7			EA. 6	LB 273.6				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

INTERCHANGE #1 QUECHEE

PROJECT: HARTFORD-SHARON-ROYALTON
PROJECT NO.: IM IR 089-1(8)

DESIGN FILE NAME: tq008sum.dgn
IPARM FILE NAME: tq008s23.i
SURVEYED BY:
SQUAD LEADER: ABK

PLOT DATE: 09-NOV-2000
SURVEY DATE:
DRAWN BY: JHK
SHEET: 225 OF 260