STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75	2.0	2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
INT #1 US 4 6.42 I T	QUECHEE 6		72"	10"	5									X																				D1-1		F-123
	WOODSTOCK 10		72"	10"	5																												D1-1		E-123
	RUTLAND 42		72"	10"	5						2			X																				D1-1		F-123
INT #1 US 4 6.43 MED			24"	30"	5																												R4-7		F-142
			18" 18"	18" 18"	2.25 2.25						1			X																				OM-1 OM-1 MOUNT BACK TO BACK		E-150 E-150
INT #1 US 4 6.46 RT	WH. RIVER JCT. 3		72"	10"	5																												D1-1		E-123
	SHARON 13		72"	10"	5																												D1-1		E-123
	BARRE 40		72"	10"	5						2			X																				D1 1		E-123
INT #1 US 4 6.49 RT	NORTH NORTH		24" 24"	12" 12"	2 2						1			X																				M3-1 M3-1 MOUNT BACK TO BACK		E-135 F-135
	89 89		24" 24"	12" 12"	4 4																												M1-1 M1-1 MOUNT BACK TO BACK		E-135 E-135
			21" 21"	15" 15"	2.19 2.19						2			X									2	X									M6-1 M6-1 MOUNT BACK TO BACK		E-135 E-135
INT #1 US 4 6.49 I T	TO		24"	12"	2																												M4-5		F-135
	WEST SOUTH		24" 24"	12" 12"	2 2																												M3-4 M3-3		E-136 E-135
	4 89		24" 24"	24" 24"	4 4						2			X									2	X									M1-4 M1-1		E-136 E-135
INT #1 US 4 6.50 MED			24"	30"	5																												R4-7 MOUNT FACING OPPOSITE TRAFFIC		E-142
			18" 18"	18" 18"	2.25 2.25						1			X		X																	OM-1 OM-1 MOUNT BACK TO BACK		E-150 E-150
												FT	FT	FT 98	FT	FT	FT		EA	LB	LB	LB		LB 516.8	LB	LB	LB							
	TOTALS		SF 79.38	SF	EA.	SF						FT 98			FT					LB			EA. 4	LB 516.8				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

INTERCHANGE #1 QUECHEE

PROJECT: HARTFORD-SHARON-ROYALTON
PROJECT NO.: IM IR 089-1(8)

DESIGN FILE NAME: tq008sum.dgn
IPARM FILE NAME: tq008s25.i
SURVEYED BY:
SQUAD LEADER: ABK

PLOT DATE: 09-NOV-2000
SURVEY DATE:
DRAWN BY: JHK
SHEET: 227 OF 260