STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75	2.0	2.5 lb/ft 1.88	2.16	3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0	4.0	4.0 MOD lb/ft 1.3	1.7	1.7	TUBULAR STEEL Ø (in) FOUNDATION	3.0	3.5	4.0	5.0 lb/ft 7.6	9.0	10.8	14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																																
INT #2 RAMP D RT	TURN SIGNAL REQUIRED BEFORE CHANGING LANES		36"	36"	9																																			VR 002		E-142
	PROHIBITED		36"	36"	9						1			~~X~~																										VR-046		E-142
INT #2 RAMP D RT			24"	24"	4						1			X																										R3-2 MOUNT ACROSS FROM GORE		E-143
INT #2 VT RT 14 4.91 RT	JCT TO		21" 24"	15" 12"	2.19 2																																		M2-1 M4-5		E-136C E-135
	132 INTERSTATE 89		30" 24"	24" 24"	5 4																																		M1-6 M1-1		E-136C E-135
			21"	15"	2.19						2			X																								X	M5-1 SEE STD E-123 FOR MOUNTING DETAIL		E-135
INT #2 VT RT 14 4.94 LT	W. HARTFORD 6		72"	10"	5						2			X																										D1-1		E-123
INT #2 VT RT 14 4.95 RT	S. ROYALTON 5		72"	10"	5																																		D1-1		E-123
	S. STRAFFORD 6		72"	10"	5																																		D1-1		E-123
	BARRE 30		72"	10"	5						2			X																										D1-1		E-123
INT #2 VT RT 14 4.98 LT	SOUTH		24"	12"	2																																		M3-3		E-136B
	VERMONT 14		24"	24"	4						1			X																										M1-5		E-136B
INT #2 VT RT 14 4.99 RT	NORTH EAST TO		24" 24" 24"	12" 12" 12"	2 2 2																																		M3-1 M3-2 M4-5		E-136B E-136C E-135
	VERMONT 14 132 INTERSTATE 89		24" 24" 30"	24" 24" 24"	4 4 5																																		M1 5 M1 6 M1 1		E-136B E-136C E-135
			21" 21" 21"	15" 15" 15"	2.19 2.19 2.19						2																		2	X								X	M6-3 M6-1 SEE STD E-123 FOR MOUNTING DETAIL M6-1		E-136B E-136C E-135
INT #2 VT RT 14 4.99 RT	EAST TO SOUTH		24" 24" 24"	12" 12" 12"	2 2 2																																		M3 2 M4 5 M3 3		E-136B E-136C E-135
												FT	FT	FT 126	FT	FT	FT		EA	LB	LB	LB		LB 198	LB	LB	LB													
TOTALS			SF 94.95	SF	EA.	SF						FT 126			FT					LB				EA. 2	LB 198				EA.	EA.	LB									

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

INTERCHANGE #2 SHARON

PROJECT: HARTFORD-SHARON-ROYALTON
PROJECT NO.: IM IR 089-1(8)

DESIGN FILE NAME: †a008sum.dgn
IPARM FILE NAME: †a008s30.i
SURVEYED BY:
SQUAD LEADER: ABK
PLOT DATE: 09-NOV-2000
SURVEY DATE:
DRAWN BY: JHK
SHEET: 232 OF 260