STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (In)	SIGN DIMENSIONS HEIGHT (In)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.0 lb/ft 2.16	SQUARE STEEL (In) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (In) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (In) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (In) FOUND-ATION	TUBULAR STEEL Ø (In) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (In) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (In) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (In) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	REQUIRED SIGN	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																							
	← →		21" 21"	15" 15"	2.19 2.19						2											2	X								X	M6-1 M6-1 SEE STD E-123 FOR MOUNTING DETAIL		E-136B E-136B
INT #2 RTE. 132 0.07 RT	↑ STRAFFORD 9		72"	10"	5																											D1-1		E-123
	← BARRE 30		72"	10"	5																											D1-1		E-123
	← BETHEL 12		72"	10"	5																											D1-1		E-123
	WH. RIVER JCT. 13 →		72"	10"	5						2			X																		D1-1		E-123
INT #2 RTE. 132 0.10 LT	SPEED LIMIT 30		24"	30"	5						1			X																		R2-1		E-142
INT #2 RTE. 132 0.10 LT	JCT		21"	15"	2.19																											M2-1 MOUNT OUTBOARD OF SL 30 SIGN		E-136B
	VERMONT 14		24"	24"	4																											M1-5		E-136B
	END		21"	15"	2.19																											M4-6		E-140
	132		30"	24"	5						1									X												M1-6		E-136C
INT #2 RTE. 132 0.13 RT	EAST NORTH SOUTH		24" 24" 24"	12" 12" 12"	2 2 2																											M3-2 M3-1 M3-3		E-135
	132 INTERSTATE 89 INTERSTATE 89		30" 24" 24"	24" 24" 24"	5 4 4																											M1-6 M1-1 M1-1		E-135
	↑ ↑ →		21" 21" 21"	15" 15" 15"	2.19 2.19 2.19						2											2	X								X	M6-3 M6-3 SEE STD E-123 FOR MOUNTING DETAIL M6-1		E-135
INT #2 RTE. 132 0.15 LT	SOUTH		24"	12"	2																											M3-3		E-135
	INTERSTATE 89		24"	24"	4																											M1-1		E-135
	←		21"	15"	2.19						1									X												M6-1		E-135
												FT	FT	FT 42	FT	FT	FT		EA	LB 49.4	LB	LB		LB 547.2	LB	LB	LB							
TOTALS					SF 76.52	SF	EA.	SF				FT 42			FT					LB 49.4			EA. 4	LB 547.2				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

INTERCHANGE #2 SHARON

PROJECT: HARTFORD-SHARON-ROYALTON	PROJECT NO.: IM IR 089-1(8)
DESIGN FILE NAME: †a008sum.dgn IPARM FILE NAME: †a008s32.I SURVEYED BY: SQUAD LEADER: ABK	PLOT DATE: 09-NOV-2000 SURVEY DATE: DRAWN BY: JHK SHEET: 234 OF 260