STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (In)	SIGN DIMENSIONS HEIGHT (In)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.0 lb/ft 2.16	SQUARE STEEL (In) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (In) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (In) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (In) FOUND-ATION	TUBULAR STEEL Ø (In) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (In) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (In) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (In) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	REFOUNDATION REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																							
INT #2 RTE. 132 0.19 RT	NORTH		24"	12"	2																													M3-1		E-135
	INTERSTATE 89		24"	24"	4																													M1-1		E-135
	←		21"	15"	2.19						1									X														M6-1		E-135
INT #2 RTE. 132 0.21 LT	WEST SOUTH NORTH		24" 24" 24"	12" 12" 12"	2 2 2																													M3-4 M3-3 M3-1		E-136C E-135 E-135
	132 INTERSTATE 89 INTERSTATE 89		30" 24" 24"	24" 24" 24"	5 4 4																													M1-6 M1-1 M1-1		E-136C E-135 E-135
	↑ ↑ →		21" 21" 21"	15" 15" 15"	2.19 2.19 2.19						2												2	X								X		M6-3 M6-3 SEE STD E-123 FOR MOUNTING DETAIL M6-1		E-136C E-135 E-135
INT #2 RTE. 132 0.23 RT	EAST		24"	12"	2																													M3-2		E-136C
	132		30"	24"	5						1			X																				M1-6		E-136C
INT #2 RTE. 132 0.23 RT	STATE HIGHWAY ENDS STATE HIGHWAY BEGINS		24" 24"	18" 18"	3 3																													VR-038 VR-039		E-141 E-141
	THROUGH WAY ENDS HERE THROUGH WAY BEGINS HERE		24" 24"	24" 24"	4 4						1			X																				VR-041 VR-040 MOUNT BACK TO BACK		E-141 E-141
INT #2 RTE. 132 0.24 RT	SHOULDER NARROWS		36"	36"	9						1			X																				D1-1		E-151
INT #2 RTE. 132 0.24 LT	↑ SHARON 2		72"	10"	5																													D1-1		E-123
	← WH. RIVER JCT. 13		72"	10"	5																													D1-1		E-123
	BETHEL 12 →		72"	10"	5																													D1-1		E-123
	BARRE 30 →		72"	10"	5						2			X																				D1-1		E-123
												FT	FT	FT 70	FT	FT	FT		EA	LB 24.7	LB	LB		LB 258.4	LB	LB	LB								
		TOTALS	SF 83.76	SF	EA.	SF						FT 70			FT					LB 24.7			EA. 2	LB 258.4				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

INTERCHANGE #2 SHARON

PROJECT: HARTFORD-SHARON-ROYALTON	PROJECT NO.: IM IR 089-1(8)
DESIGN FILE NAME: tq008sum.dgn IPARM FILE NAME: tq008s33.i SURVEYED BY: SQUAD LEADER: ABK	PLOT DATE: 09-NOV-2000 SURVEY DATE: DRAWN BY: JHK SHEET: 235 OF 260