



BRIDGE #15N (NORTHBOUND)
 LEFT ELEVATION - FACING FROM CENTER OF ROADWAY
 ALL DIMENSIONS SHOWN ARE ALONG CURVE
 APROXIMATE RADIUS = 2,439 ft.
 PAY LENGTH = 195'-6 3/8" (THIS SHEET)
 TOTAL PAY LIMIT ITEM 525.33 (STEEL BRIDGE RAIL, NETC 2-RAIL) = 8665 LF

NOTES:

1. ALL TUBING IS STRAIGHT, NO SHOP CURVING NECESSARY TO FIT BRIDGERAIL TUBES ALONG REQUIRED RADIUS.
2. ALL DIMENSIONS HAVE BEEN DEVELOPED FROM CONTRACT PLANS ONLY.
3. CONTRACTOR MUST FIELD-VERIFY DIMENSIONS PRIOR TO APPROVAL.

REVISIONS		
No.	Remarks	Date
0	Initial submittal	1/26/01
1	FINAL "AS-BUILT"	11/8/01



ITEM 525.33 - BRIDGE RAILING NETC 2-RAIL		DRAWN P. Radice
IM IR 089-1(8)		CHECKED <i>[Signature]</i>
WINDSOR COUNTY		DATE 1/23/01
TOWNS OF HARTFORD, SHARON & ROYALTON		SCALE NONE
INTERSTATE ROUTE 89		HSC REFERENCE NO.
		1239
GENERAL CONTRACTOR	MORRILL CONSTRUCTION INC.	SIZE D REVISION Δ
SUB CONTRACTOR	F.R. LAFAYETTE INC.	SHEET NO.
		7 of 24