QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

APPROXIMATE SUMMARY OF QUANTITIES

			NON-GOV'T. PARTICIPATION	TRAINING	EROSION CONTROL	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
						1	1	LS	CLEARING AND GRUBBING	201.10	EST.
						100	100	EA	REMOVING SMALL TREES	201.15	EST.
						1	1	ACR	THINNING AND TRIMMING	201.30	EST.
						8	8	EA	THINNING AND TRIMMING (MOD.)	201.31	-
						1550	1550	CY	COMMON EXCAVATION	203.15	36
						68800	68800	CY	SOLID ROCK EXCAVATION	203.16	14
						2400	2400	CY	EARTH BORROW	203.30	6
						150	150	CY	SAND BORROW	203.31	2
						2000	2000	CY	GRANULAR BORROW	203.32	28
						1500	1500	SY	FINE GRADING SUBGRADE	203.40	EST.
					70	1000	1070	CY	TRENCH EXCAVATION OF EARTH	204.20	EST.
						65	65	CY	TRENCH EXCAVATION OF ROCK	204.21	2.8
						5550	5550	CY	STRUCTURE EXCAVATION	204.25	34
						100	100	CY	GRANULAR BACKFILL FOR STRUCTURES	204.30	EST.
						6300	6300	SY	COLD PLANING-BIT. PAVEMENT	210.10	EST.
						60	60	CY	SUBBASE OF CRUSHED GRAVEL (COARSE GRADED)	301.25	8
						2850	2850	CY	SUBBASE DENSE GRADED CRUSHED STONE	301.35	35
						850	850	CY	AGGREGATE SURFACE COURSE	401.10	37
						3200	3200	TON	BITUMINOUS CONCRETE PAVEMENT	406.25	59
						80	80	CY	CONCRETE, CLASS B	501.25	4.2
						5000	5000	SF	TEMPORARY SHEET PILING (0 PEOPLE PASS)	505.36	EST.
						3240	3240	LB	REINFORCING STEEL	507.15	3
						10	10	CY	REMOVAL OF CONCRETE OR MASONRY	529.25	0.1
						20	20	LF	12'' CSP .064	601.0005	EST.
						40	40	LF	15'' CSP .064	601.0010	EST.
						116	116	LF	18'' CSP .064	601.0015	EST.
						42	42	LF	24'' CSP .064	601.0025	EST.
						60	60	LF	30'' CSP .079	601.0036	EST.
						36	36	LF	36'' CSP .079	601.0046	EST.
						10	10	LF	48'' CSP .109	601.0057	EST.
						94	94	LF	18'' PCCSP .064	601.0415	EST.
						220	220	LF	24'' PCCSP .064	601.0425	EST.
						10	10	LF	42'' PCCSP .109	601.0452	EST.
						40	40	LF	48'' PCCSP .109 (W/VERTICAL RISER)	601.0457	EST.
						40	40	LF	18'' RCP CLASS III	601.0815	EST.

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

STATIONS		PAVEMENT WIDTHS			EQUATIONS		FEET	MILES	REMARKS
FROM	TO				+	-			
TOTALS									

2-JUN-1992 REVISED, 87A025QSI

PROJECT NAME SPRINGFIELD-HARTFORD
PROJECT NUMBER IR 091-1(20)