QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

APPROXIMATE SUMMARY OF QUANTITIES

			NON-GOV'T. PARTICIPATION	TRAINING	EROSION CONTROL	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
						50	50	HR	BULLDOZER RENTAL, TYPE I	608.10	EST.
			100				100	HR	BULLDOZER RENTAL, TYPE II (MOD.)	608.11	EST.
									(STOCKPILING LEDGE @ OFF PROJECT SITES).		
						900	900	HR	DRAGLINE RENTAL, TYPE II	608.21	EST.
					10	140	150	HR	ALL PURP. EXCAVATOR RENTAL, TYPE I	608.25	EST.
						800	800	HR	ALL PURP. EXCAVATOR RENTAL, TYPE II	608.26	EST.
					20	1000	1020	HR	TRUCK RENTAL	608.37	EST.
						800	800	HR	TRUCK RENTAL (MOD.)	608.37	EST.
						900	900	HR	LOADER RENTAL TYPE II	608.41	EST.
					350		350	CY	STONE FILL, TYPE I	613.10	40
					550		550	CY	STONE FILL, TYPE II	613.11	16
					25		25	CY	STONE FILL, TYPE III	613.12	2
						50	50	TON	BIT. CONCRETE CURB, TYPE A	616.30	EST.
						850	850	LF	TREATED TIMBER CURB	616.35	12
						355	355	LF	REMOVING AND RESETTING CURB	616.40	EST.
						950	950	LF	REMOVAL OF EXISTING CURB	616.41	EST.
						15	15	SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5''	618.10	EST.
						40	40	EA	BOUNDARY MARKERS	619.10	EST.
						115	115	EA	STEEL MARKER POST	619.16	EST.
						39000	39000	LF	CHAIN-LINK FENCE, 6 FEET	620.12	278
						25	25	LF	GATE FOR CHAIN-LINK FENCE, 6 FEET	620.16	EST.
						150	150	EA	BRACING ASSEMBLY FOR CHAIN-LINK FENCE, 6 FEET	620.21	EST.
						248500	248500	LF	WOVEN WIRE FENCE WITH STEEL POSTS	620.25	209
						1	1	EA	DRIVE GATE FOR WOVEN WIRE FENCE	620.30	EST.
						1250	1250	EA	STEEL BRACE FOR WOVEN WIRE FENCE	620.40	EST.
						2510	2510	LF	SNOW BARRIER - GALVANIZED	620.75	6
						300	300	LF	STEEL BEAM GUARD RAIL (STEEL POSTS)	621.20	EST.
						10	10	EA	BREAKAWAY CABLE TERMINAL	621.50	EST.
						8	8	EA	ANCHOR FOR STEEL BEAM GUARD RAIL	621.60	EST.
						1309	1309	LF	REMOVING AND RESET GUARD RAIL	621.75	
						50	50	EA	REPLACE GUARD RAIL POST ASSEMBLY	621.76	EST.
						625	625	LF	REPLACE GUARD RAIL BEAM UNIT	621.77	EST.
						2450	2450	LF	REMOVAL AND DISPOSAL OF GUARD RAIL	621.80	0
						10	10	EA	REMOVAL AND DISPOSAL OF GUIDE POSTS	621.81	EST.
						16026	16026	LF	TEMPORARY TRAFFIC BARRIER	621.90	EST.

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

STATIONS FROM	STATIONS TO	PAVEMENT WIDTHS			EQUATIONS +	EQUATIONS -	FEET	MILES	REMARKS
TOTALS									16-MAR-1992 87A025QS3

PROJECT NAME SPRINGFIELD-HARTFORD
PROJECT NUMBER IR 091-1(20)