QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

APPROXIMATE SUMMARY OF QUANTITIES

			NON-GOV'T. PARTICIPATION	TRAINING	EROSION CONTROL	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
						2500	2500	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
						5000	5000	HR	FLAGGERS	630.15	EST.
						1	1	LS	FIELD OFFICE-ENGINEERS	631.10	
						1	1	LS	TESTING EQUIPMENT - CONCRETE	631.16	
						1	1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	
				1500			1500	HR	EMPLOYEE TRAINEESHIP	634.10	EST.
						1	1	LS	MOBILIZATION	635.10	EST.
						1	1	LS	TRAFFIC CONTROL	641.10	EST.
						6930	6930	LF	4'' DURABLE WHITE LINES	646.40	EST.
						6060	6060	LF	4'' DURABLE YELLOW LINES	646.41	EST.
						31300	31300	LF	TEMPORARY 4'' WHITE LINE, (TAPE)	646.60	34
						32500	32500	LF	TEMPORARY 4'' YELLOW LINE, (TAPE)	646.61	56
						700	700	LF	TEMPORARY 8'' WHITE LINE, (TAPE)	646.62	-
						5	5	EA	TEMPORARY LETTER OR SYMBOL	646.70	-
						6584	6584	EA	RAISED PAVEMENT MARKERS, TYPE II	646.81	EST.
						13808	13808	SF	REMOVAL OF EXISTING PVT. MARKINGS	646.82	EST.
						320	320	SY	GEOTEXTILE FOR ROADBED SUBGRADE SEPARATOR	649.11	15
					200		200	SY	GEOTEXTILE FOR SILT FENCE	649.51	EST.
					600		600	LB	SEED	651.15	
					4000		4000	LB	FERTILIZER	651.18	
					20		20	TON	AGRICULTURAL LIMESTONE	651.20	
					20		20	TON	HAY MULCH	651.25	
					100		100	EA	HAY BALES FOR EROSION CONTROL	651.26	
					5000		5000	SY	EROSION MATTING	654.10	
						75	75	SF	TRAFFIC SIGNS , TYPE A	675.20	0.4
						85	85	SF	TRAFFIC SIGNS , TYPE B	675.21	0.4
						771	771	LB	FLANGED CHANNEL SIGN POSTS	675.30	-
						4025	4025	LB	TUBULAR STEEL SIGN POSTS	675.33	3.8
						30	30	EA	FOUNDATION FOR TUBULAR STEEL POSTS	675.43	-
						62	62	EA	REMOVING SIGNS	675.50	-
						58	58	EA	ERECTING SALVAGED SIGNS	675.60	-
						60	60	EA	REMOVE AND REPLACE REFLECTOR UNITS	676.15	EST.
						20	20	EA	REMOVE AND REPLACE REFLECTOR UNITS - MOD.	676.15	EST.

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

STATIONS		PAVEMENT WIDTHS			EQUATIONS		FEET	MILES	REMARKS
FROM	TO				+	-			
TOTALS									

10-MAR-1992 87A0250S4

PROJECT NAME SPRINGFIELD-HARTFORD
PROJECT NUMBER IR 091-1(20)