

SOUTHBOUND

ITEM DETAIL SUMMARY SHEET FOR SPRINGFIELD - HARTFORD IR 091-1(20)

SOUTHBOUND

MILE MARKER	MILE MARKER	POS.	SOLID ROCK EXCAV.	COMM. EXCAV.	TRENCH EXCAV.		EARTH BORROW	AGGREG. SURFACE COURSE	CLEAN. CULV. PIPE L.F.	CORRUGATED STEEL PIPE			REINFORCED CONCRETE PIPE			RELAY PIPE	6" UND.	CONC. CL B CY	REIN. STEEL LBS	GRATE TYPE A EA	CHAN. ELEV EA	BIT. CONC. PAV'T.	SNOW FENCE	GUARDRAIL ITEMS		STONE FILL			GRAN-ULAR BORROW	SUBBASE OF CRUSHED GRAVEL	REMARKS
					EARTH CY	ROCK CY				D	L	TH	D	L	CL									621.80	621.75	TYPE I	TYPE II	TYPE III			
41.85		MED.							5											1											RAISE CURB DI
41.90		MED.							5												1										RAISE CURB DI
41.97		OUT.							5												1										RAISE CURB DI
41.97		MED.							5												1										RAISE CURB DI
42.01		MED.							5												1										RAISE CURB DI
42.06		MED.							5												1										RAISE CURB DI
42.09		MED.							5												1										RAISE CURB DI
42.15		OUT.																						25							REPAIR DAMAGED GUARDRAIL
42.17		MED.				5.0											3.0	270	1												CONSTRUCT NEW R.C.D.I. & REDIRECT FLOW WITH NEW CSP INTO ADJACENT GORE AREA AS PER RESIDENT ENGINEER. BACKFILL EXISTING TRANS-MEDIAN DITCH WITH EARTH BORROW WITHIN THE 30' CLEAR ZONE.
42.38		OUT.							5												1										RAISE CURB DI
42.43		OUT.							5												1										RAISE CURB DI
42.73		OUT.							5												1										RAISE CURB DI
42.76		CL																													CROWN POINT ROAD PEDESTRIAN PASS. ALL QUANTITIES, N.B. & S.B. LISTED ON N.B. ITEM DETAIL SHEET, SEE LAYOUT AND SECTIONS.
42.82		OUT.							5												1										RAISE CURB DI
42.86		OUT.							5												1										RAISE CURB DI
42.97		OUT.							5												1										RAISE CURB DI
42.97		MED.							5												1										RAISE CURB DI
43.03		OUT.							5												1										RAISE CURB DI
43.27		OUT.							5												1										RAISE CURB DI
43.33		OUT.							5												1										RAISE CURB DI
43.37		OUT.							5												1										RAISE CURB DI
43.42		OUT.							5												1										RAISE CURB DI
43.47		MED.				3.0																									REMOVE HEADWALL (ITEM 529.25) & REPLACE WITH 18' M.E.S.
43.59		OUT.							5												1										RAISE CURB DI
43.61		MED.							5												1										RAISE CURB DI
43.64		OUT.							5												1										RAISE CURB DI
43.65		MED.							5												1										RAISE CURB DI
43.77		MED.							5												1										RAISE CURB DI
44.25	44.28	OUT.																													REMOVE ALL TREES WITHIN CLEAR ZONE, PAY AS THINNING AND TRIMMING.
44.34	44.45	OUT.	3009																												LEDGE REMOVAL AREA, REFER TO SITE SPECIFIC SECTIONS.
SHEET TOTALS			3009	-	8		11	-	120	24	26	.064	-	-	-	-	3.0	270	1-A	24	-	-	25	-	-	-	-	-	-	-	

SURVEYED BY _____ DATE _____
 DRAWN BY _____ DATE _____
 SQUAD LEADER D.F. HALE
 DESIGN FILE NO. ZFA2155.501 87A025.DGN
 PRF FILE 87A025S07 DATE PLOTTED 31-JAN-1992
 PROJ. NAME SPRINGFIELD-HARTFORD
 PROJ. NO. IR 091-1(20)
 SHEET 18 OF 133 SHEETS